

AD-A096 386

NAVAL POSTGRADUATE SCHOOL MONTEREY CA  
EFFECTS OF OSCILLATION FREQUENCY AND AMPLITUDE ON SEPARATION IN--ETC(U)  
SEP 80 M FOX


F/G 20/4

UNCLASSIFIED

NL

1 OF 2

NO  
CONTENTS



AD A 096386

(2) LEVEL II

NAVAL POSTGRADUATE SCHOOL  
Monterey, California



DTIC  
ELECTE  
MAR 16 1981  
S B D

THESIS

6 EFFECTS OF OSCILLATION FREQUENCY  
AND AMPLITUDE ON SEPARATION IN  
AN UNSTEADY TURBULENT FLOW,

by

10 Martin/Fox 12/10/80

// September, 1980

Thesis Advisor:

J. A. Miller

Approved for public release; distribution unlimited

1376 FILE COPY

81 3 16 094

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO.	3. RECIPIENT'S CATALOG NUMBER
	AD-A096 386	
4. TITLE (and Subtitle) Effects of Oscillation Frequency and Amplitude on Separation in an Unsteady Turbulent Flow		5. TYPE OF REPORT & PERIOD COVERED Master's Thesis; September, 1980
		6. PERFORMING ORG. REPORT NUMBER
7. AUTHOR(s) Martin Fox		8. CONTRACT OR GRANT NUMBER(s)
9. PERFORMING ORGANIZATION NAME AND ADDRESS Naval Postgraduate School Monterey, California 93940		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS
11. CONTROLLING OFFICE NAME AND ADDRESS Naval Postgraduate School Monterey, California 93940		12. REPORT DATE September, 1980
		13. NUMBER OF PAGES 99
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) Naval Postgraduate School Monterey, California 93940		15. SECURITY CLASS. (of this report) Unclassified
		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE
16. DISTRIBUTION STATEMENT (of this Report) Approved for public release; distribution unlimited		
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Turbulent Boundary Layer Oscillating Flow		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) A two-dimensional model was developed and used in a preliminary investigation of the relationship between flow oscillation frequency, oscillation amplitude, and turbulent boundary layer separation in a low speed, oscillating wind tunnel. It was found that the frequency of oscillation had a profound effect upon the amplitude of oscillation and flow separation. Frequencies from 20 Hz to 28 Hz and 70 Hz to 80 Hz		

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

20. ABSTRACT (continued)

allowed attachment of the boundary layer, while other frequencies, up to 100 Hz, caused flow separation in an eighteen degree divergent section.

Accession For	
THIS GRADE	✓
DATE	
BY	
NO.	
AVAIL.	YES
Dist.	to
A	

Unclassified

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

Approved for public release; distribution unlimited

Effects of Oscillation Frequency  
and Amplitude on Separation in  
an Unsteady Turbulent Flow

by

Martin Fox  
Lieutenant, United States Navy  
B.S.A.E., Auburn University, 1973

Submitted in partial fulfillment of the  
requirements for the degree of

MASTER OF SCIENCE IN AERONAUTICAL ENGINEERING

from the

NAVAL POSTGRADUATE SCHOOL  
September, 1980

Author

Martin Fox

Approved by:

James H. Tuller  
Thesis Advisor

Max F. Platzer  
Chairman, Department of Aeronautics

William M. Tolles  
Dean of Science and Engineering

# ABSTRACT

A two-dimensional model was developed and used in a preliminary investigation of the relationship between flow oscillation frequency, oscillation amplitude, and turbulent boundary layer separation in a low speed, oscillating wind tunnel.

It was found that the frequency of oscillation had a profound effect upon the amplitude of oscillation and flow separation. Frequencies from 20 Hz to 28 Hz and 70 Hz to 80 Hz allowed attachment of the boundary layer, while other frequencies, up to 100 Hz, caused flow separation in an eighteen degree divergent section.

## TABLE OF CONTENTS

LIST OF TABLES . . . . .	7
LIST OF FIGURES . . . . .	8
LIST OF SYMBOLS . . . . .	10
ACKNOWLEDGEMENTS . . . . .	11
I. INTRODUCTION . . . . .	12
II. EXPERIMENTAL EQUIPMENT . . . . .	14
A. OSCILLATING FLOW WIND TUNNEL . . . . .	14
1. General Description . . . . .	14
2. Flow Oscillation System . . . . .	15
B. MODELS . . . . .	20
1. Preliminary Models . . . . .	20
2. Primary Models . . . . .	20
C. INSTRUMENTATION . . . . .	24
1. Freestream Flow Sensors . . . . .	24
2. Model Surface Flow Sensor . . . . .	24
a. Preliminary Model . . . . .	24
b. Primary Model . . . . .	27
c. Ten-Channel Hot-Wire Probe . . . . .	27
III. EXPERIMENTAL PROCEDURE . . . . .	32
A. DETERMINATION OF PRIMARY MODEL GEOMETRY . . . . .	32
1. Freestream Flow Characteristics . . . . .	32
a. Mean Tunnel Velocity . . . . .	32

b.	Frequency of Oscillation . . . . .	32
c.	Amplitude of Oscillation . . . . .	33
2.	Boundary Layer Separation on Preliminary Model . . . . .	33
3.	Design of Primary Model . . . . .	34
B.	PRESSURE DISTRIBUTION ON PRIMARY MODEL . . . . .	35
C.	BOUNDARY LAYER CHARACTERISTICS . . . . .	36
IV.	RESULTS . . . . .	38
A.	PRELIMINARY MODEL . . . . .	38
1.	Oscillation Amplitude Versus Frequency . . . . .	38
2.	Boundary Layer Activity . . . . .	38
B.	PRIMARY MODEL . . . . .	40
1.	Pressure Distribution . . . . .	40
2.	Boundary Layer . . . . .	48
V.	CONCLUSIONS . . . . .	55
	APPENDIX EXPERIMENTAL DATA . . . . .	57
	LIST OF REFERENCES . . . . .	98
	INITIAL DISTRIBUTION LIST . . . . .	99



## LIST OF TABLES

TABLE I	Measured Dimensionless Oscillation Amplitude as a Function of Frequency . . .	57
TABLE II	Experimental Oscillation Frequencies and Amplitudes Data . . . . .	58
TABLE III	Measured Surface Pressures . . . . .	63
TABLE IV	Pressure Survey Data . . . . .	86

## LIST OF FIGURES

1	Plan View of Wind Tunnel . . . . .	16
2	Overall Photographic View of the Wind Tunnel . . . . .	18
3	Photograph of the Rotating Shutter Valve . . . . .	19
4	Preliminary Model . . . . .	21
5	Typical Tunnel Test Section Velocity . . . . .	23
6	Primary Model . . . . .	25
7	Primary Model in Test Section . . . . .	26
8	Hot-Wire Probe . . . . .	28
9	Typical Hot-Wire Anemometer Calibration Curve (Steady Flow) . . . . .	30
10	Typical Hot-Wire Anemometer Calibration Velocity Profile in Blasius Flow . . . . .	31
11	Freestream Oscillation Frequency Versus Amplitude . . . . .	39
12	Pressure Distribution -- 67 Per Cent Blockage . . . . .	42
13	Pressure Distribution -- 67 Per Cent Blockage . . . . .	43
14	Pressure Distribution -- 67 Per Cent Blockage . . . . .	44
15	Pressure Distribution -- 98 Per Cent Blockage . . . . .	46
16	Pressure Distribution -- 98 Per Cent Blockage . . . . .	47

17	Typical Oscillographs . . . . .	51
18	Typical Oscillographs . . . . .	52
19	Typical Oscillographs . . . . .	53
20	Typical Oscillographs . . . . .	54

# LIST OF SYMBOLS

c	model chord length (inches)
$C_p$	nondimensional coefficient of pressure - $C_p = \frac{p - p_o}{\frac{1}{2} \rho \bar{U}^2}$
f	flow oscillation frequency - Hertz (Hz)
$N_A$	nondimensional flow oscillation amplitude - $N_A = \frac{\Delta u}{\bar{U}}$
p	static pressure (lbf/ft <sup>2</sup> )
$p_o$	freestream ambient pressure (lbf/ft <sup>2</sup> )
q	test section dynamic pressure (lbf/ft <sup>2</sup> ) $q = \frac{1}{2} \rho \bar{U}^2$
T	freestream ambient temperature (°F)
u	streamwise component of tunnel velocity (ft/sec)
$\Delta u$	velocity fluctuation (ft/sec)
$\bar{U}$	mean tunnel velocity (ft/sec)
x	streamwise model dimension taken from leading edge (inches)
$x/c$	normalized model location
y	dimension normal to flow (inches)
$\rho$	air density (lbm/ft <sup>3</sup> )
$\nu$	kinematic viscosity (ft <sup>2</sup> /sec)

### ACKNOWLEDGEMENTS

The author wishes to express his gratitude to Dr. James A. Miller, Associate Professor of Aeronautics, for his thoughtful guidance during the present work.

Grateful acknowledgement is also due to the technical engineering staff, and in particular to Messrs. Theodore B. Dunton and Robert A. Besel, for their constant and cheerful cooperation and assistance throughout this study.

## I. INTRODUCTION

Increased interest in the design and development of vertical/short takeoff and landing (V/STOL) aircraft has magnified the need to fully understand the complex flow fields associated with their aerodynamic and propulsive systems. The unique capabilities of such vehicles require significant portions of their flight profiles to be performed with much of the aircraft immersed in turbulent flow. When in operation near the ground or landing platform, unsteady, turbulent flow may become the dominant phenomenon.

Given the importance of this area of study and the limitations of the analytical solutions, there is a surprisingly small body of empirical work concerned with unsteady boundary layers caused by freestream flow oscillation. This is perhaps due to a lack of suitable test facilities; that is, facilities that are capable of a wide range of freestream oscillation frequencies and amplitudes. However, significant advances were made by Karlsson [Ref. 1] who showed that flow oscillation had little effect on the mean velocity profile of the turbulent boundary layer, and Nickerson [Ref. 2] who used hot-wire anemometry in his study of the laminar boundary layer on a flat plate. Despard [Ref. 3] studied the separation of a laminar boundary layer using a flow oscillation system developed by Miller [Ref. 4]. Recently, Telionis [Ref. 5]

used hot-wire anemometry to investigate the separation and reattachment of boundary layers in unsteady conditions.

The purpose of this investigation was to develop a wind tunnel model useful in determining the effects of various flow oscillation frequencies upon the amplitude of the oscillation and their relationship, if any, to the separation of a turbulent boundary layer. It was also desired to perform initial testing on the equipment associated with a hot-wire anemometry study of the turbulent boundary layer.

## II. EXPERIMENTAL EQUIPMENT

### A. OSCILLATING FLOW WIND TUNNEL

#### 1. General Description

The low-speed, oscillating flow wind tunnel located in the Aeronautics Laboratories of the Naval Postgraduate School was utilized for this study. This wind tunnel is of the open circuit design, with a 24-inch square by 223-inch long test section. The tunnel inlet is 8-feet square, resulting in a 16:1 contraction ratio. Three high solidity screens located in the inlet section upstream of the nozzle produce measured freestream turbulence intensities of from 0.261 to 0.413 per cent for the test velocities.

The wind tunnel drive consists of two Joy Axivane Fans in series, each of which has an internal 100 horsepower, direct connected, 1750 rpm motor. The fan blades are internally adjustable through a pitch range of 25 to 55 degrees, providing a wide operating range. Each fan has a separate set of variable inlet vanes that are multi-leaf in design and are remotely adjustable to afford fine control of test section mean velocity during tunnel operation. The tunnel velocity range is from 10 to 250 feet per second, although the maximum mean velocity used for this study was 148 feet per second. The inlet vanes are set to preswirl the air flow in the direction of fan rotation in order to




reduce fanloads. To minimize wall deflections caused by large and almost instantaneous changes in static pressure, the test section upper and lower walls are constructed of continuous pieces of two-inch thick aluminum, 24 inches wide and 223 inches in length. The test section wall facing the tunnel control console is composed of three hinged, two-inch thick, stress relieved Lucite panels. The Lucite doors, while normally secured in the closed position by twelve large bolts per panel during tunnel operation, may be hydraulically raised for access to the test section. The back wall of the test section is also composed of three panels that are manually removable in order to facilitate model installation. For this experimental study, the upstream back wall panel was made of Lucite and the two downstream panels were constructed of two-inch thick plywood to allow for instrumentation installation.

A plan view of the oscillating flow wind tunnel is shown in Figure 1. An overall photographic view of the tunnel as seen from downstream of the fan inlet vanes is shown in Figure 2.

## 2. Flow Oscillation System

A sinusoidal velocity component is introduced into the mean freestream flow by harmonic solid blockage variations downstream of the test section. This is accomplished by the use of four horizontal, rotating shutter blades that completely span the trailing edge of the test section. Four steel shafts,



PLAN VIEW OF WIND TUNNEL

FIGURE 1

equidistant from each other and the test section walls, are slotted to accept various width flat blades, thereby forming a variable sized, multi-slotted, butterfly-type valve. A photographic view of the shutters looking downstream from the test section is shown in Figure 3. The use of this type of shutter system to produce flow oscillations through a large range of frequencies and amplitudes was employed by Karlsson [Ref. 17], and is identical to that employed by Miller [Ref. 47]. The drive for the shutter system is a five horsepower variable speed electric motor coupled to the bottom shaft of the shutter system via a belt and pulley system in order to produce a wide variety of frequencies. The upper three shutter shafts are connected to each other and the driven shaft by timing belts to insure that all four shutters rotate in phase. The total range of remotely selectable shutter frequencies is from 0.1 to 240 Hertz. This investigation employed frequencies of from 1 to 100 Hertz.

Gross oscillation amplitude may be changed by the installation of one of several sets of shutter blades having different widths and therefore different blockage ratios. The range of test section blockage produced by the various shutter blades was from 25 to 98 per cent. This investigation primarily utilized test section blockage of 67 and 98 per cent, resulting in amplitude variations of from 3 to 108 per cent of the mean freestream velocity. The shutters fixed in the fully open position cause a non-oscillatory blockage of approximately five per cent.




FIGURE 2  
OVERALL PHOTOGRAPHIC VIEW OF THE WIND TUNNEL




FIGURE 3  
PHOTOGRAPH OF THE ROTATING SHUTTER VALVE.

## B. MODELS

### 1. Preliminary Models

In order to effectively investigate the effects of unsteady flow on turbulent boundary layer separation, it was necessary to develop a model that would produce boundary layer separation in the neighborhood of a location in which the instrumentation could be conveniently introduced. In order to accomplish this, several possible model geometries were inexpensively constructed and tested in order to evolve a configuration to be employed on a more fully instrumented, and rugged, primary model.


The preliminary models were of all wood construction and were two-dimensional shapes spanning the width of the test section, mounted to the floor of the test section, causing convergence and divergence of the section. The models all used a 54-inch long 6-inch thick main body with provisions for interchangeable leading and trailing edge sections. Several leading/trailing edge sections were constructed with inclines of 12, 18, and 24 degrees. Figure 4 is a sketch of a preliminary model showing the main body with 24 degree leading and trailing edge sections installed. During the preliminary study, the trailing edge section was tufted for visual indications of turbulent flow and boundary layer separation.

### 2. Primary Model

Based on the results of the preliminary investigation, a primary model was designed.

# PRELIMINARY MODEL

SIDE VIEW



REAR VIEW





FIGURE 4

The primary model was constructed of a continuous upper surface skin of 0.100-inch thick aluminum, 62.5 inches long, which was welded to three continuous pieces of 0.25-inch thick aluminum forming three bulkheads, which were then welded to a single, flat 0.25-inch aluminum deck. The primary model was of the same general shape as the preliminary model, with an 18 degree inclined trailing edge and parabolic leading edge. Ports were cut into the six-inch high bulkheads to facilitate service of surface pressure instrumentation and to afford access to the bolts mounting the model to the tunnel floor.

Along the port side, looking forward, twenty-seven .040-inch static pressure ports were positioned four inches from the test section wall. These pressure ports ran from 22 inches aft of the leading edge in two-inch intervals until just forward of the point of the after-body ramp, where they were positioned each inch, terminating 2.5 inches from the trailing edge. The lateral positioning of these ports was determined from measured velocity profiles shown in Figure 5 [Ref. 3] in order to be outside the wall boundary layer and at the same time to leave the centerline of the model free of ports and avoid interference with the multi-channel hot-wire probe.

Two, two-inch wide, 25.5-inch long strips of 0.040-inch thick steel were imbedded into the model skin to enable a magnetically mounted multi-channel, hot-wire anemometer





TYPICAL TUNNEL TEST SECTION VELOCITY PROFILE

(  $U_{max} = 20$  ft/sec )

FIGURE 5

probe to be easily positioned for boundary layer surveys. Figure 6 shows the relative positions of the steel tracks and the pressure ports.

Figure 7 shows the primary model in position in the test section of the wind tunnel with the instrumentation installed.

### C. INSTRUMENTATION

#### 1. Freestream Flow Sensors

A standard pitot-static tube and a hot-wire anemometer probe were located six inches above the model at mid-chord of both the preliminary and primary models to determine mean freestream velocity. Dynamic pressure was read from a Meriam micro-manometer for the preliminary model, and from a 50-tube water manometer used also to measure the surface pressure distribution for the primary model. The freestream turbulence was measured with a linearized hot-wire anemometer described in Ref. 3.


The frequency of the shutter rotation, and therefore, the frequency of flow oscillation, was measured with a digital counter which read an electrical signal developed by an optical system employing a stationary point light source and a rotating chopper wheel fixed to the top shutter valve shaft.

#### 2. Model Surface Flow Sensors

##### a. Preliminary Model

The principal method of investigation for the preliminary model was the observation of tufts attached to

SIDE VIEW



PRIMARY MODEL

TOP VIEW




FIGURE 6




FIGURE 7  
PRIMARY MODEL IN THE TEST SECTION

the divergent section. In order to facilitate these observations, a stroboscopic light was electrically triggered by a contact on the uppermost shutter shaft to permit an optical freezing of the motion of the tufts in the oscillating flow. The stroboscopic light trigger was mounted on a rotatable base assembly which allowed the tuft action to be viewed at any phase of the shutter cycle.

b. Primary Model

The surface pressure distribution over the aft two-thirds of the primary model was measured by 27 static pressure ports on the model surface. The first 11 of these ports were located on the constant area section of the model, with the remaining 16 ports located on the diverging section. Pressures at these ports were read, along with the freestream dynamic pressure, on a 50-tube water manometer calibrated in centimeters.

c. Ten-Channel Hot-Wire Probe

In order to investigate the boundary layer along the surface of the primary model, an aluminum carriage supporting ten constant temperature hot-wire anemometer probes was employed. Each hot-wire could be individually positioned from the surface to approximately three inches above the surface. The carriage stood on magnetic feet that matched the steel tracks in the model. This allowed a continuous chordwise traverse of the probe from six inches upstream of the point of divergence to approximately two inches





FIGURE 8  
HOT-WIRE PROBE

from the trailing edge. During oscillating flow tunnel operation, the probe exhibited a tendency to "walk" along its magnetic track. In order to overcome this, a simple support rig was installed consisting of a single threaded rod, mounted to the hot-wire carriage and a streamlined stand, anchored to the tunnel floor aft of the model. Figure 8 shows the hot-wire probe in position of the model.

The ten-channel hot-wire circuits were identical to the one employed in the freestream hot-wire. Figure 9 is a typical calibration curve for non-oscillating flow, and Figure 10, a typical calibration in Blasius flow, as demonstrated by Despard [Ref. 3] and Allen [Ref. 6].

Each sensing element was a 0.00015-inch diameter tungsten filament one-eighth-inch long copper plated at its ends to facilitate mounting. The effective sensing length of each wire was approximately 0.080 inches.

Signals representing total instantaneous velocities were produced at the outputs due to the DC coupled circuitry of the anemometers. The oscillating velocity components of the total velocity are proportional to the alternating current component of the anemometer output, and were displayed on a Tektronix 555 Dual Beam oscilloscope. The oscilloscope was equipped with two, four-channel preamplifiers, permitting a maximum of eight hot-wire outputs to be viewed simultaneously. A Tektronix oscilloscope camera was used to record the multi-channel display.



TYPICAL HOT WIRE ANEMOMETER CALIBRATION CURVE  
(STEADY FLOW)

FIGURE 9






FIGURE 10

TYPICAL HOT WIRE ANEMOMETER CALIBRATION  
VELOCITY PROFILE IN BLASIIUS FLOW

### III. EXPERIMENTAL PROCEDURE

#### A. DETERMINATION OF PRIMARY MODEL GEOMETRY

##### 1. Freestream Flow Characteristics

Prior to investigating the boundary layer characteristics of the preliminary model, it was necessary to determine the operating ranges of the freestream flow variables in oscillating flow with the model installed in the test section. The flow variables of interest were: mean tunnel velocity, frequency of oscillation, and amplitude of oscillation.

##### a. Mean Tunnel Velocity

In order to insure a turbulent boundary layer over the trailing edge of the model, mean tunnel velocities of 111 feet per second, 132.37 feet per second, and 148.16 feet per second, were set and maintained via the variable inlet vanes and measured with the pitot tube. These velocities yielded Reynolds numbers, under average ambient conditions of  $3.8 \times 10^6$ ,  $4.5 \times 10^6$ , and  $5.1 \times 10^6$  for a characteristic length of 70 inches.

##### b. Frequency of Oscillation

Shutter rotation frequencies, and therefore, flow oscillation frequencies, of from 1 to 100 Hertz were investigated in the initial testing. The frequencies were measured by the previously described electro-optical system and were read directly from the digital frequency counter. Shutter frequency

was varied from one to six Hertz in one Hertz increments, and from 20 to 100 Hertz in two Hertz increments for a single mean velocity. The frequency range of from 6 to 20 Hertz was not investigated due to shutter drive gearing difficulties. Oscillation frequency was then retarded from 100 Hertz to one Hertz by reversing the above procedure while maintaining a constant mean tunnel velocity.

c. Amplitude of Oscillation

The amplitude of oscillation was measured with the single-channel freestream hot-wire anemometer and the AC component was read with a Ballantine true RMS voltmeter. These readings were of change in streamwise velocity normalized with freestream mean velocity ( $N_A$ ). Amplitude readings were taken at each frequency while traversing the frequency range in the upward direction, then confirmed while descending the frequency range.

Several experimental runs were made at each of the mean velocities with two full data collection runs made for each of the lower mean velocities, and one for the highest velocity. Due to instrument fluctuations experienced at frequencies less than four Hertz, the oscillation amplitude values for the lowest frequencies were considered at best approximate and were not reported.

2. Boundary Layer Separation on Preliminary Model

The paramount purpose of the preliminary investigation was to determine the combination of leading and trailing edge

sections that would give rise to turbulent boundary layer separation on the trailing edge section. The use of tufts on the trailing edge sections was believed to be the most reliable and expedient method to study the desired phenomenon, given the lack of instrumentation incorporated into the preliminary model.

It became clear early in the testing that the leading edge section had no real effect upon the desired conditions, therefore, the 24-degree leading edge section was fixed in position for the duration of the experiment.

The trailing edge sections were affixed with tufts, as shown in Figure 4, and the model was run through the range of freestream conditions. The stroboscopic light was connected to the shutter shaft and cam, and was positioned so as to effectively light the tufts. The reaction of the tufts to the flow was visually studied to determine the effects of flow oscillation on boundary layer separation. Numerous experimental runs were made with the several trailing edge sections under the various freestream conditions and with stroboscopic and normal lighting.

### 3. Design of Primary Model

From the results of the preliminary investigation, it was concluded that the primary model should be of similar dimensions to those of the preliminary model with a trailing edge incline of 18 degrees to best produce a turbulent boundary layer that would separate at the desired location

under test conditions. Due to structural difficulties experienced with the wooden preliminary models, it was also concluded that the primary model should be designed with increased strength. The primary model constructed under the above criteria was somewhat smaller in the chordwise dimension than the preliminary model. The shorter chordwise dimension positioned the divergent section of the model 45 inches from the leading edge. This shortening of the chord for the primary model allowed a single test section panel bolting and unbolting requirement for maintenance ease, but still produced a sufficiently high Reynolds number at one-half of the lowest preliminary test mean velocity. Jacobs [Ref. 7] determined that a turbulent boundary layer would occur at a Reynolds number of approximately  $1.0 \times 10^6$  for a flat plate, in this identical wind tunnel under similar test conditions. The primary model would experience a Reynolds number of  $1.2 \times 10^6$  at the point of divergence with a mean velocity of 55 feet per second.

#### B. PRESSURE DISTRIBUTION ON PRIMARY MODEL

The pressure distribution over the primary model from a position 22 inches aft of the leading edge to the trailing edge was determined by use of static pressure ports and a manometer board. Several runs were made with both the 67 per cent and 98 per cent occlusion shutter blades installed. The frequency values used for data collection were 1, 2, 4, 6, and 25 Hertz, for both sets of shutter blades, 30 to 100 Hertz,

and 30 to 70 Hertz, in ten Hertz increments, for the 67 per cent and 98 per cent blades respectively. Considering that the nondimensional coefficient of pressure ( $C_p$ ) was to be the ultimate output of these runs, mean tunnel velocity was not necessarily kept constant throughout the frequency range.

A maximum freestream oscillation amplitude at six Hertz was noted during this phase of the experiment as being 108 per cent, while using the large shutter blades.

### C. BOUNDARY LAYER CHARACTERISTICS

The boundary layer over the model was monitored to ensure turbulent flow with the aide of the ten-channel hot-wire probe and the eight-trace oscilloscope. Evidence of turbulent flow was taken to be the characteristic oscilloscope trace for turbulence as discussed by Bradshaw [Ref. 8].

Prior to each experimental run, calibration of the hot-wire anemometers was carried out in situ. The positioning of the boundary layer probe's wires with respect to height above the model was then set. The final setting of the individual anemometers was accomplished after the calibration in consideration of the possibility that one or more of the wires may have failed the calibration procedure. The wire heights could then be adjusted so as to provide adequate coverage of the boundary layer without the need to remove the entire probe for repair. For the purposes of this initial investigation, a meaningful run could be made with the free-stream anemometer and five of the boundary layer anemometers

being in calibration. The heights above the model surface, for this worst-case hot-wire availability, were a wire each at 0.05, 0.10, 0.20, 0.30, and 0.40 inches.

The wind tunnel was set to operate with an oscillation frequency of 20 Hertz, oscillation amplitude of 18 per cent, mean velocity of 15 feet per second, and the large shutter blades installed. Photographs of the multi-trace oscilloscope were taken with the hot-wire carriage set at various chordwise positions. After completing this overall chordwise survey, the carriage was positioned five inches downstream of the point of model divergence. This mean freestream velocity was then varied from 22 to 88 feet per second, and the oscillation frequency varied from 20 to 70 Hertz, to complete this initial turbulent boundary layer survey.

#### IV. RESULTS

##### A. PRELIMINARY MODEL

###### 1. Oscillation Amplitude Versus Frequency

The data collected from the freestream amplitude investigation for the selected mean velocities indicates that the mean velocity had little or no effect upon the nondimensional amplitude factor,  $N_A$ . A study of the data shows that for a specific oscillation frequency ( $f$ ), the values obtained for  $N_A$  were usually within one per cent of each other for any of the mean velocities tested. Due to this similarity, the values of amplitudes, for a given frequency, were arithmetically averaged in order to be plotted against oscillation frequency. Figure 11 is the graph of oscillation amplitude versus oscillation frequency for a tunnel occlusion of 67 per cent.

Figure 11 reveals the bulk of the values of  $N_A$  to lie between 5 and 15 per cent. Values larger than 15 per cent are seen to have occurred at 21 - 22 Hz, and 90 - 94 Hz. Other, less prominent, peaks occurred in the vicinity of 30 Hz, 40 Hz, and 80 Hz.

###### 2. Boundary Layer Activity

The tufting of the preliminary model, as shown in Figure 4, clearly evidenced a turbulent boundary layer in existence over the area of interest in the case of the 18 and



FREESTREAM OSCILLATION  
FREQUENCY VS AMPLITUDE




FIGURE 11

24 degree diverging model sections. Close study of the 24 degree section showed that the boundary layer remained attached to the Row 1 area (Figure 4) as oscillation began from steady flow conditions. The boundary layer remained attached in this area until approximately 28 Hz when the entire diverging section became stalled. The fully stalled condition continued through approximately 70 Hz, when the Row 1 area again showed turbulent boundary layer attachment. The entire section again became fully stalled at the 80 Hz reading and remained so through the test limit of 100 Hz.

The 18 degree diverging section displayed similar frequency response but the turbulent boundary layer attachment point had moved into the Row 2 and 3 area.

These results were quite repeatable and consistent throughout the range of mean velocities (111 - 148 ft/sec).

## B. PRIMARY MODEL

### 1. Pressure Distribution

A surface pressure survey was conducted with both the 67 per cent and the 98 per cent flow blockage shutter blades installed. The range of oscillation frequency ( $f$ ) was 1 Hz to 100 Hz for the former and 1 Hz to 70 Hz for the latter shutter blade configuration. To preclude physical damage, the larger occlusion tests were limited to the 70 Hz level due to violent tunnel behavior above this value. In fact, data was collected at 80 Hz with the 98 per cent blades installed,

but, due to equipment vibration, that data point was not repeated and therefore considered unreliable.

Figures 12, 13, and 14 depict the pressure coefficient ( $C_p$ ) measured at each of the 27 pressure ports from 31.2 to 96 per cent chord for the case of 67 per cent flow blockage. The peak of these curves (lowest value of  $C_p$ ) occurs uniformly at port number 11 which was located just upstream of the point of model divergence at 67 per cent chord. As may be seen, the  $C_p$  curves remain generally smooth throughout the frequency range with all values of  $C_p$  remaining more positive than the steady state ( $f = 0$  Hz) values.

The curves for frequencies of one Hz, two Hz, and four Hz were identical to the curve for six Hz and were not presented. As may be seen, the curve for six Hz is nearly identical to the steady state value.

The values for 25 Hz, 40 Hz, and 80 Hz are also nearly identical to each other. The curves of 30 Hz, 50 Hz, and 90 Hz duplicate each other and are somewhat less negative than the 25 Hz series. The values for 100 Hz stand alone at the most positive edge of the family.

The differences between the curves becomes generally less pronounced downstream of the point of model divergence. The values for 6 Hz, 25 Hz, and 30 Hz all merge at the 90 per cent chord point. The 50 Hz and 60 Hz curves become nearly coincident aft of 70 per cent chord. A similar situation occurs for the 90 and 100 Hz  $C_p$  values.

# PRESSURE DISTRIBUTION PRIMARY MODEL




FIGURE 12

# PRESSURE DISTRIBUTION PRIMARY MODEL




FIGURE 13.

# PRESSURE DISTRIBUTION PRIMARY MODEL




FIGURE 14

Figures 15 and 16 present the pressure coefficient versus chord for the 98 per cent occlusion shutter blades. Here the one Hz and two Hz values track very closely with the steady flow  $C_p$  curve.

This family of curves behaves much differently than the 67 per cent blockage curves. In general, there is a much larger range of values of  $C_p$  over the frequency range than the smaller blockage, and the curves tend to be much more erratic in their behavior. Except as noted, no two curves are alike.

The curve depicting an  $f$  of four Hz begins at values much less negative than the steady state case, joining it at the point of model divergence and then dropping sharply off until the 80 per cent chord point where it again rises to become more negative than steady state only to immediately fall off to a  $C_p$  value of nearly zero.

The six Hz curve is nearly identical to the shape of the four Hz curve with the exception that the  $C_p$  value remains constant until approximately 70 per cent chord. The six Hz curve also fluctuates at 80 per cent chord then drops off sharply to  $C_p$  values near +0.5.

As the oscillation frequency is increased, the curves become less erratic in their behavior. The 25 Hz curve shows some of the tendencies of the 4 and 6 Hz curves, but at a reduced level. The 60 Hz curve is nearly flat, while the 70 Hz curve is indeed a straight line until approximately 90 per cent chord, where it slowly increases.

# PRESSURE DISTRIBUTION PRIMARY MODEL




FIGURE 15.



# PRESSURE DISTRIBUTION PRIMARY MODEL




FIGURE 16

It should be noted that the large water manometer board was well suited for this investigation due to the natural damping of its measurements. It was relatively simple to obtain the pressure data without the averaging necessary with a faster response system, especially at the higher frequencies.

## 2. Boundary Layer

The turbulent boundary layer investigation performed on the primary model was designed as a preliminary check on apparatus suitability, operating procedures, and identification of potential problems for future study of the flow phenomenon. With these goals in mind, several series of experimental runs were performed with the ten-channel hot-wire probe, and all associated equipment in position and operating.

It was found that the setup and electronic calibration of the probe could be performed efficiently and accurately after a short initial learning period. This included the manual setting of individual anemometer heights and identification of any broken or questionable hot-wires.

The security of the probe on its magnetic feet and steel traverse was improved considerably by the addition of the supporting rod and stand. The probe was easy to move to any position and was secure in that position throughout the frequency range of from 20 Hz to 70 Hz at several mean velocities.

The satisfactory performance of the primary model and its measuring equipment was demonstrated during a


simulated data collection run. Figures 17 - 20 are typical of the oscillographs taken from the multi-trace oscilloscope during this final experiment. The uppermost trace depicts the freestream flow read from the test section single hot-wire anemometer. The second through fifth trace shows the boundary layer flow at 0.05 inches, 0.10 inches, 0.20 inches, and 0.30 inches above the model surface. The sixth trace, if present, depicts the boundary layer at 0.40 inches above the model. The tunnel was run with the 98 per cent occlusion shutter blades installed.

The freestream conditions for Figures 17 and 18 were mean velocity set at 42 feet per second, oscillation frequency set at 20 Hz, yielding an oscillation amplitude of 18 per cent. The variable in the four oscillographs is the location of the probe on the model. The range of locations shown are from 2 inches upstream of the model divergence point, ( $x/c = .67$ ), to 14 inches downstream, ( $x/c = .93$ ).

The oscillographs in Figure 19 and the upper one in Figure 20 are for a fixed probe location of five inches downstream of the model divergence point, ( $x/c = .78$ ). Mean tunnel velocity was increased to 51.4 feet per second and frequency was made the variable. Note the increase in oscillation amplitude for the 20 Hz case. It was shown for the 67 per cent occlusion blades that the mean freestream velocity had no effect upon the value of  $N_A$ . The lower oscillograph in Figure 20 is at the same conditions as the 20 Hz


oscillograph of Figure 19 with the exception that the mean velocity was increased to 103 feet per second. The oscillation amplitude, however, remained the same as the 51.4 feet per second case.

It is clear that the boundary layer was entirely turbulent throughout this test.




$f = 20 \text{ Hz}$   
 $x/c = .67$   
 $\bar{U} = 42 \text{ ft/s}$   
 $N_A = 18\%$

TYPICAL OSCILLOGRAPHS



$f = 20 \text{ Hz}$   
 $x/c = .78$   
 $\bar{U} = 42 \text{ ft/s}$   
 $N_A = 18\%$

FIGURE 17



$f = 20 \text{ Hz}$   
 $x/c = .84$   
 $\bar{U} = 42 \text{ ft/s}$   
 $N_A = 18\%$

TYPICAL OSCILLOGRAPHS

$f = 20 \text{ Hz}$   
 $x/c = .93$   
 $\bar{U} = 42 \text{ ft/s}$   
 $N_A = 18\%$





FIGURE 18



$f = 20 \text{ Hz}$   
 $x/c = .78$   
 $\bar{U} = 51.4 \text{ ft/s}$   
 $N_A = 35\%$

TYPICAL OSCILLOGRAPHS

$f = 40 \text{ Hz}$   
 $x/c = .78$   
 $\bar{U} = 51.4 \text{ ft/s}$   
 $N_A = 39\%$





FIGURE 19.



$f = 60 \text{ Hz}$   
 $x/c = .78$   
 $\bar{U} = 51.4 \text{ ft/s}$   
 $N_A = 29\%$

TYPICAL OSCILLOGRAPHS

$f = 20 \text{ Hz}$   
 $x/c = .77$   
 $\bar{U} = 103 \text{ ft/s}$   
 $N_A = 35\%$




FIGURE 20



## V. CONCLUSIONS

From the results described above, the following conclusions may be drawn:

Oscillation amplitude is clearly a function of oscillation frequency in this tunnel and may increase dramatically with little change in frequency. The amplitude change of from less than 5 per cent at 88 Hz to over 27 per cent at 90 Hz is certain evidence of this fact.

The effect of mean freestream velocity upon oscillation amplitude, when coupled with large flow occlusions, is not clear. The mean freestream velocity showed to have no noticeable effect upon amplitude in the 67 per cent flow occlusion study; however, the 98 per cent occlusion tests showed mixed results. The amplitude doubled with a 22 per cent increase in tunnel velocity at one point, but then remained constant with a 100 per cent increase in mean velocity.

Turbulent boundary layer separation over a two-dimensional body may be affected by flow oscillation frequency. The results of the tuft experiment support this conclusion.

The primary model design and construction is satisfactory for the investigation of the effect of freestream oscillation on turbulent boundary layer separation.

The ten-channel hot-wire boundary layer probe performed well, but due to the large aerodynamic forces capable of being produced by the tunnel, should be adequately braced in the streamwise direction.

## APPENDIX

## EXPERIMENTAL DATA

TABLE I

MEASURED DIMENSIONLESS  
OSCILLATION AMPLITUDE AS  
A FUNCTION OF FREQUENCY

f (HZ)	N <sub>A</sub> (%)	f (HZ)	N <sub>A</sub> (%)
4	18.0	60	4.0
5	15.0	62	5.8
6	11.5	64	7.9
21	15.5	66	7.6
24	8.8	68	7.0
26	5.6	70	6.5
28	6.3	72	5.6
30	11.5	74	5.8
32	9.3	76	11.0
34	9.0	78	13.0
36	8.5	80	14.3
38	9.1	82	8.2
40	9.4	84	7.2
42	11.5	86	5.9
44	13.4	88	5.6
46	9.0	90	27.3
48	9.7	92	17.3
50	18.7	94	15.2
52	11.7	96	12.8
54	7.0	98	11.6
56	5.5	100	5.5
58	4.5		

- NOTE: 1. Data reduced from raw data by arithmetic averaging.  
 2. f is Oscillation Frequency in Hertz.  
 3. N<sub>A</sub> is nondimensional Oscillation Amplitude ( $\Delta u/\bar{u}$ ).

TABLE II

EXPERIMENTAL OSCILLATION  
FREQUENCIES AND  
AMPLITUDES DATA

q = 7 cm H<sub>2</sub>O

p = 29.98 in Hg

T = 70°F

f (HZ)	N <sub>A</sub> (%)	f (HZ)	N <sub>A</sub> (%)
4	17.5	60	5.0
5	15.5	62	6.5
6	11.0	64	8.5
22	15.0	66	8.0
24	8.0	68	7.5
26	5.0	70	7.0
28	5.0	72	6.0
30	11.0	74	5.0
32	9.0	76	13.0
34	8.5	78	15.0
36	8.5	80	16.0
38	9.5	82	8.5
40	10.0	84	8.0
42	11.0	86	7.0
46	8.5	88	6.5
48	9.5	90	25.0
50	18.0	92	17.0
52	13.0	94	15.0
54	6.5	96	13.5
56	5.5	98	12.0
58	4.5	100	5.0

TABLE II (continued)

EXPERIMENTAL OSCILLATION  
FREQUENCIES AND  
AMPLITUDES DATA

 $q = 7 \text{ cm H}_2\text{O}$  $p = 29.98 \text{ in Hg}$  $T = 70^\circ\text{F}$ 

$f$ (HZ)	$N_A$ (%)	$f$ (HZ)	$N_A$ (%)
4	18.0	60	5.0
5	15.0	62	6.5
6	11.5	64	9.0
21	16.5	66	8.5
24	8.5	68	7.5
26	5.0	70	6.5
28	5.5	72	6.0
30	11.5	74	5.5
32	9.0	76	12.0
34	9.0	78	14.5
36	8.5	80	15.5
38	9.0	82	8.0
40	9.5	84	7.0
43	12.5	86	6.0
46	8.5	88	5.5
48	9.5	90	30.0
50	19.0	92	20.0
54	6.0	94	17.0
56	5.0	98	13.5
58	4.5	100	7.0

TABLE II (continued)

EXPERIMENTAL OSCILLATION  
FREQUENCIES AND  
AMPLITUDES DATA

q = 10 cm H <sub>2</sub> O		p = 30.00 in Hg		T = 68°F	
f (HZ)	N <sub>A</sub> (%)	f (HZ)	N <sub>A</sub> (%)		
21	14.0	62	4.5		
23	13.5	64	6.5		
24	10.0	66	7.0		
26	7.0	68	6.8		
28	8.0	70	6.5		
30	11.5	72	5.2		
32	10.0	74	6.0		
34	9.5	76	9.8		
36	9.0	78	10.5		
38	9.5	80	13.0		
40	9.5	82	8.5		
44	14.0	84	7.0		
46	9.5	86	5.5		
48	10.0	88	5.0		
50	18.0	90	27.0		
52	11.0	92	19.0		
54	8.0	94	15.0		
56	6.0	96	12.0		
58	4.8	98	10.0		
60	3.5	100	5.0		

TABLE II (continued)

EXPERIMENTAL OSCILLATION  
FREQUENCIES AND  
AMPLITUDES DATA

 $q = 10 \text{ cm H}_2\text{O}$  $p = 30.00 \text{ in Hg}$  $T = 68^\circ\text{F}$ 

$f$ (HZ)	$N_A$ (%)	$f$ (HZ)	$N_A$ (%)
22	14.5	64	7.0
24	9.5	66	7.5
26	6.5	68	7.0
28	7.0	70	6.5
30	12.0	72	6.0
32	9.5	74	6.5
34	9.5	76	10.0
36	8.5	78	11.5
38	8.5	80	14.0
40	9.0	82	8.5
44	13.5	84	7.5
46	10.0	86	6.0
48	10.0	88	5.5
50	18.5	90	28.5
52	11.0	92	19.5
54	8.5	94	16.0
56	6.0	96	13.0
58	5.0	98	11.0
60	3.5	100	6.0
62	5.5		

TABLE II (continued)

EXPERIMENTAL OSCILLATION  
FREQUENCIES AND  
AMPLITUDES DATA

q = 12.5 cm H <sub>2</sub> O		p = 29.99 in Hg		T = 69°F	
f (HZ)	N <sub>A</sub> (%)	f (HZ)	N <sub>A</sub> (%)	f (HZ)	N <sub>A</sub> (%)
4	19.0	58	3.5		
5	14.5	60	3.0		
6	12.0	64	8.5		
21	16.0	66	7.0		
24	8.0	68	6.5		
26	4.5	70	6.0		
28	6.0	72	5.0		
30	11.5	74	6.0		
32	9.0	76	10.5		
34	8.5	80	13.0		
36	8.0	82	7.5		
40	9.0	84	6.5		
44	13.0	86	5.0		
46	8.0	88	5.5		
48	9.5	90	26.0		
50	20.0	92	15.0		
54	6.5	94	13.0		
56	5.0	100	4.5		



TABLE III

## MEASURED SURFACE PRESSURES

68 ° F HZ ATMOS PRESS (PSF) 2115.7848 TUNNEL PRESS (PSF) 2074.8728 TUNNEL O (PSF) 40.912 TUNNEL VELOC (FPS) 187.1977485							
PORT # 1	PORT # 10	PORT # 19		PORT # 2	PORT # 11	PORT # 20	
X/C= 0.352	X/C= 0.64	X/C= 0.632		X/C= 0.672	X/C= 0.848	X/C= 0.848	
PORT PRESS= 1997.54912	PORT PRESS= 1999.59472	PORT PRESS= 2024.14192		PORT PRESS= 1993.45792	PORT PRESS= 2026.16752	PORT PRESS= 2026.16752	
CP= -1.89	CP= -1.84	CP= -1.24		CP= -1.99	CP= -1.19	CP= -1.19	
PORT # 3	PORT # 12	PORT # 21		PORT # 4	PORT # 13	PORT # 22	
X/C= 0.416	X/C= 0.72	X/C= 0.864		X/C= 0.736	X/C= 0.88	X/C= 0.88	
PORT PRESS= 2001.64032	PORT PRESS= 2001.64032	PORT PRESS= 2027.21032		PORT PRESS= 2004.70872	PORT PRESS= 2028.23312	PORT PRESS= 2028.23312	
CP= -1.79	CP= -1.79	CP= -1.15		CP= -1.715	CP= -1.14	CP= -1.14	
PORT # 5	PORT # 14	PORT # 23		PORT # 6	PORT # 15	PORT # 24	
X/C= 0.48	X/C= 0.752	X/C= 0.896		X/C= 0.768	X/C= 0.912	X/C= 0.912	
PORT PRESS= 2003.68592	PORT PRESS= 2009.4136	PORT PRESS= 2039.25592		PORT PRESS= 2068.736	PORT PRESS= 2031.30152	PORT PRESS= 2031.30152	
CP= -1.74	CP= -1.6	CP= -1.115		CP= -0.15	CP= -1.065	CP= -1.065	
PORT # 7	PORT # 16	PORT # 25		PORT # 8	PORT # 17	PORT # 26	
X/C= 0.544	X/C= 0.784	X/C= 0.928		X/C= 0.8	X/C= 0.944	X/C= 0.944	
PORT PRESS= 2003.68592	PORT PRESS= 2014.93672	PORT PRESS= 2032.32432		PORT PRESS= 2016.98232	PORT PRESS= 2033.34712	PORT PRESS= 2033.34712	
CP= -1.74	CP= -1.465	CP= -1.04		CP= -1.415	CP= -1.015	CP= -1.015	
PORT # 9	PORT # 18	PORT # 27		PORT # 10	PORT # 19	PORT # 28	
X/C= 0.608	X/C= 0.816	X/C= 0.96		X/C= 0.816	X/C= 0.96	X/C= 0.96	
PORT PRESS= 2001.64032	PORT PRESS= 2022.09632	PORT PRESS= 2033.9608		PORT PRESS= 2022.09632	PORT PRESS= 2033.9608	PORT PRESS= 2033.9608	
CP= -1.79	CP= -1.29	CP= -1		CP= -1.29	CP= -1	CP= -1	

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BLADES			
1 NZ	68 TEMP (F)		
	ATMOS PRESS (PSF) 2115.7848		
	TUNNEL PRESS (PSF) 2105.5568		
	TUNNEL Q (PSF) 10.228		
	TUNNEL VELOC (FPS) 93.59887025		
PORT # 1	PORT # 10	PORT # 19	
X/C = 0.352	X/C = 0.64	X/C = 0.832	
PORT PRESS = 2086.53272	PORT PRESS = 2087.1464	PORT PRESS = 2092.2604	
CP = -1.86	CP = -1.8	CP = -1.3	
PORT # 2	PORT # 11	PORT # 20	
X/C = 0.384	X/C = 0.672	X/C = 0.848	
PORT PRESS = 2086.94184	PORT PRESS = 2085.1008	PORT PRESS = 2092.87408	
CP = -1.82	CP = -2	CP = -1.24	
PORT # 3	PORT # 12	PORT # 21	
X/C = 0.416	X/C = 0.72	X/C = 0.864	
PORT PRESS = 2087.55552	PORT PRESS = 2087.55552	PORT PRESS = 2092.87408	
CP = -1.76	CP = -1.76	CP = -1.24	
PORT # 4	PORT # 13	PORT # 22	
X/C = 0.448	X/C = 0.736	X/C = 0.88	
PORT PRESS = 2087.76008	PORT PRESS = 2088.57832	PORT PRESS = 2093.2832	
CP = -1.74	CP = -1.66	CP = -1.2	
PORT # 5	PORT # 14	PORT # 23	
X/C = 0.48	X/C = 0.752	X/C = 0.896	
PORT PRESS = 2087.96464	PORT PRESS = 2089.60112	PORT PRESS = 2093.48776	
CP = -1.72	CP = -1.56	CP = -1.18	
PORT # 6	PORT # 15	PORT # 24	
X/C = 0.512	X/C = 0.768	X/C = 0.912	
PORT PRESS = 2087.96464	PORT PRESS = 2090.41936	PORT PRESS = 2093.69232	
CP = -1.72	CP = -1.48	CP = -1.16	
PORT # 7	PORT # 16	PORT # 25	
X/C = 0.544	X/C = 0.784	X/C = 0.928	
PORT PRESS = 2087.96464	PORT PRESS = 2090.82848	PORT PRESS = 2094.10144	
CP = -1.72	CP = -1.44	CP = -1.12	
PORT # 8	PORT # 17	PORT # 26	
X/C = 0.576	X/C = 0.8	X/C = 0.944	
PORT PRESS = 2088.57832	PORT PRESS = 2091.2376	PORT PRESS = 2094.306	
CP = -1.66	CP = -1.4	CP = -1.1	
PORT # 9	PORT # 18	PORT # 27	
X/C = 0.608	X/C = 0.816	X/C = 0.96	
PORT PRESS = 2087.55552	PORT PRESS = 2091.64672	PORT PRESS = 2094.51056	
CP = -1.76	CP = -1.36	CP = -1.08	

TABLE III (continued)

## MEASURED SURFACE PRESSURES

2 HC		67 PER CENT BLUES	
68	TEDE (F)		
TUNNEL PRESS (PSF) 2115.7848			
TUNNEL PRESS (PSF) 2106.5796			
TUNNEL VELOC (FPS) 9.2052			
TUNNEL VELOC (FPS) 88.79568493			
PORT # 1	PORT # 10	PORT # 19	
X/C= 0.352	X/C= 0.64	X/C= 0.832	
PORT PRESS= 2099.80568	PORT PRESS= 2090.2148	PORT PRESS= 2095.13424	
CP= -1.822222222	CP= -1.777777778	CP= -1.244444444	
PORT # 2	PORT # 11	PORT # 20	
X/C= 0.344	X/C= 0.572	X/C= 0.848	
PORT PRESS= 2090.41936	PORT PRESS= 2068.96744	PORT PRESS= 2095.53336	
CP= -1.755555556	CP= -1.911111111	CP= -1.2	
PORT # 3	PORT # 12	PORT # 21	
X/C= 0.416	X/C= 0.72	X/C= 0.864	
PORT PRESS= 2090.62392	PORT PRESS= 2096.62392	PORT PRESS= 2095.73792	
CP= -1.733333333	CP= -1.733333333	CP= -1.177777778	
PORT # 4	PORT # 13	PORT # 22	
X/C= 0.448	X/C= 0.736	X/C= 0.88	
PORT PRESS= 2091.03304	PORT PRESS= 2091.84672	PORT PRESS= 2095.94348	
CP= -1.688888889	CP= -1.622222222	CP= -1.155555556	
PORT # 5	PORT # 14	PORT # 23	
X/C= 0.43	X/C= 0.752	X/C= 0.846	
PORT PRESS= 2091.2376	PORT PRESS= 2092.2604	PORT PRESS= 2095.94348	
CP= -1.686666667	CP= -1.555555556	CP= -1.155555556	
PORT # 6	PORT # 15	PORT # 24	
X/C= 0.512	X/C= 0.768	X/C= 0.912	
PORT PRESS= 2091.2376	PORT PRESS= 2093.07864	PORT PRESS= 2096.14704	
CP= -1.686666667	CP= -1.466666667	CP= -1.133333333	
PORT # 7	PORT # 16	PORT # 25	
X/C= 0.544	X/C= 0.784	X/C= 0.928	
PORT PRESS= 2091.03304	PORT PRESS= 2093.69232	PORT PRESS= 2096.3516	
CP= -1.686666667	CP= -1.4	CP= -1.111111111	
PORT # 8	PORT # 17	PORT # 26	
X/C= 0.576	X/C= 0.8	X/C= 0.944	
PORT PRESS= 2091.64672	PORT PRESS= 2093.89688	PORT PRESS= 2096.55616	
CP= -1.622222222	CP= -1.377777778	CP= -1.088888889	
PORT # 9	PORT # 18	PORT # 27	
X/C= 0.608	X/C= 0.816	X/C= 0.96	
PORT PRESS= 2090.62392	PORT PRESS= 2094.306	PORT PRESS= 2096.75072	
CP= -1.733333333	CP= -1.333333333	CP= -1.066666667	

TABLE III (continued)

## MEASURED SURFACE PRESSURE

4 HZ			67 PER CENT BLADE		
58 TENS (CF)					
AIRS PRESS (PSF) 2115.7848					
TUNNEL PRESS (PSF) 2108.01152					
TUNNEL O. PRESS (PSF) 7.77328					
TUNNEL VELOC (FPS) 81.59760333					
PORT # 1	PORT # 10	PORT # 19	PORT # 10	PORT # 19	PORT # 28
X/C= 0.352	X/C= 0.64	X/C= 0.832	X/C= 0.64	X/C= 0.832	X/C= 0.944
PORT PRESS= 2093.48776	PORT PRESS= 2094.10144	PORT PRESS= 2097.98808	PORT PRESS= 2094.10144	PORT PRESS= 2097.98808	PORT PRESS= 2099.82912
CP= -1.868421053	CP= -1.789473684	CP= -1.39473684	CP= -1.789473684	CP= -1.39473684	CP= -1.052631579
PORT # 2	PORT # 11	PORT # 20	PORT # 11	PORT # 20	PORT # 29
X/C= 0.384	X/C= 0.672	X/C= 0.848	X/C= 0.672	X/C= 0.848	X/C= 0.944
PORT PRESS= 2093.89688	PORT PRESS= 2092.87408	PORT PRESS= 2098.80632	PORT PRESS= 2092.87408	PORT PRESS= 2098.80632	PORT PRESS= 2099.82912
CP= -1.815789474	CP= -1.947368421	CP= -1.164210526	CP= -1.947368421	CP= -1.164210526	CP= -1.052631579
PORT # 3	PORT # 12	PORT # 21	PORT # 12	PORT # 21	PORT # 30
X/C= 0.416	X/C= 0.72	X/C= 0.864	X/C= 0.72	X/C= 0.864	X/C= 0.944
PORT PRESS= 2094.306	PORT PRESS= 2094.306	PORT PRESS= 2099.01088	PORT PRESS= 2094.306	PORT PRESS= 2099.01088	PORT PRESS= 2099.82912
CP= -1.763157895	CP= -1.763157895	CP= -1.157894737	CP= -1.763157895	CP= -1.157894737	CP= -1.052631579
PORT # 4	PORT # 13	PORT # 22	PORT # 13	PORT # 22	PORT # 31
X/C= 0.448	X/C= 0.736	X/C= 0.88	X/C= 0.736	X/C= 0.88	X/C= 0.944
PORT PRESS= 2094.71512	PORT PRESS= 2095.3288	PORT PRESS= 2099.21544	PORT PRESS= 2095.3288	PORT PRESS= 2099.21544	PORT PRESS= 2099.82912
CP= -1.710526316	CP= -1.631578947	CP= -1.131578947	CP= -1.631578947	CP= -1.131578947	CP= -1.052631579
PORT # 5	PORT # 14	PORT # 23	PORT # 14	PORT # 23	PORT # 32
X/C= 0.48	X/C= 0.752	X/C= 0.896	X/C= 0.752	X/C= 0.896	X/C= 0.944
PORT PRESS= 2094.71512	PORT PRESS= 2095.94248	PORT PRESS= 2099.21544	PORT PRESS= 2095.94248	PORT PRESS= 2099.21544	PORT PRESS= 2099.82912
CP= -1.710526316	CP= -1.552631579	CP= -1.131578947	CP= -1.552631579	CP= -1.131578947	CP= -1.052631579
PORT # 6	PORT # 15	PORT # 24	PORT # 15	PORT # 24	PORT # 33
X/C= 0.512	X/C= 0.768	X/C= 0.912	X/C= 0.768	X/C= 0.912	X/C= 0.944
PORT PRESS= 2094.71512	PORT PRESS= 2096.76072	PORT PRESS= 2099.42	PORT PRESS= 2096.76072	PORT PRESS= 2099.42	PORT PRESS= 2099.82912
CP= -1.710526316	CP= -1.447368421	CP= -1.105263158	CP= -1.447368421	CP= -1.105263158	CP= -1.052631579
PORT # 7	PORT # 16	PORT # 25	PORT # 16	PORT # 25	PORT # 34
X/C= 0.544	X/C= 0.784	X/C= 0.936	X/C= 0.784	X/C= 0.936	X/C= 0.944
PORT PRESS= 2094.71512	PORT PRESS= 2096.96528	PORT PRESS= 2099.62456	PORT PRESS= 2096.96528	PORT PRESS= 2099.62456	PORT PRESS= 2099.82912
CP= -1.710526316	CP= -1.421052632	CP= -1.078947368	CP= -1.421052632	CP= -1.078947368	CP= -1.052631579
PORT # 8	PORT # 17	PORT # 26	PORT # 17	PORT # 26	PORT # 35
X/C= 0.576	X/C= 0.8	X/C= 0.944	X/C= 0.8	X/C= 0.944	X/C= 0.944
PORT PRESS= 2095.12424	PORT PRESS= 2097.3744	PORT PRESS= 2099.82912	PORT PRESS= 2097.3744	PORT PRESS= 2099.82912	PORT PRESS= 2099.82912
CP= -1.657894737	CP= -1.368421053	CP= -1.052631579	CP= -1.368421053	CP= -1.052631579	CP= -1.052631579
PORT # 9	PORT # 18	PORT # 27	PORT # 18	PORT # 27	PORT # 36
X/C= 0.608	X/C= 0.816	X/C= 0.96	X/C= 0.816	X/C= 0.96	X/C= 0.96
PORT PRESS= 2094.306	PORT PRESS= 2097.57896	PORT PRESS= 2099.82912	PORT PRESS= 2097.57896	PORT PRESS= 2099.82912	PORT PRESS= 2099.82912
CP= -1.763157895	CP= -1.342105263	CP= -1.052631579	CP= -1.342105263	CP= -1.052631579	CP= -1.052631579

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BLADES			
6 H2	68 TEMP (F)		
	ATMOSP PRESS (PSF) 2115.7848		
	TUNNEL PRESS (PSF) 2108.61152		
	TUNNEL V (PSF) 7.77328		
	TUNNEL VELOC (FPS) 81.59760333		
PORT # 1	PORT # 10	PORT # 19	
X/C= 0.352	X/C= 0.64	X/C= 0.832	
PORT PRESS= 2093.69232	PORT PRESS= 2094.10144	PORT PRESS= 2098.3972	
CP= -1.642105263	CP= -1.789473684	CP= -1.236643105	
PORT # 2	PORT # 11	PORT # 20	
X/C= 0.384	X/C= 0.672	X/C= 0.848	
PORT PRESS= 2094.306	PORT PRESS= 2092.87408	PORT PRESS= 2098.60632	
CP= -1.763157895	CP= -1.947368421	CP= -1.184210526	
PORT # 3	PORT # 12	PORT # 31	
X/C= 0.416	X/C= 0.72	X/C= 0.864	
PORT PRESS= 2094.51056	PORT PRESS= 2094.306	PORT PRESS= 2098.80632	
CP= -1.736842105	CP= -1.763157895	CP= -1.184210526	
PORT # 4	PORT # 13	PORT # 22	
X/C= 0.448	X/C= 0.736	X/C= 0.88	
PORT PRESS= 2094.71512	PORT PRESS= 2095.3288	PORT PRESS= 2099.42	
CP= -1.710526316	CP= -1.631578947	CP= -1.105263158	
PORT # 5	PORT # 14	PORT # 23	
X/C= 0.48	X/C= 0.752	X/C= 0.896	
PORT PRESS= 2095.12424	PORT PRESS= 2095.94248	PORT PRESS= 2099.42	
CP= -1.657894737	CP= -1.552631579	CP= -1.105263158	
PORT # 6	PORT # 15	PORT # 24	
X/C= 0.512	X/C= 0.768	X/C= 0.912	
PORT PRESS= 2094.91968	PORT PRESS= 2096.3516	PORT PRESS= 2099.42	
CP= -1.684210526	CP= -1.5	CP= -1.105263158	
PORT # 7	PORT # 16	PORT # 25	
X/C= 0.544	X/C= 0.784	X/C= 0.928	
PORT PRESS= 2094.71512	PORT PRESS= 2096.76072	PORT PRESS= 2099.62456	
CP= -1.710526316	CP= -1.47368421	CP= -1.078947368	
PORT # 8	PORT # 17	PORT # 26	
X/C= 0.576	X/C= 0.8	X/C= 0.944	
PORT PRESS= 2095.53336	PORT PRESS= 2097.16964	PORT PRESS= 2099.62456	
CP= -1.60263158	CP= -1.394736842	CP= -1.078947368	
PORT # 9	PORT # 18	PORT # 27	
X/C= 0.608	X/C= 0.816	X/C= 0.96	
PORT PRESS= 2094.306	PORT PRESS= 2097.57896	PORT PRESS= 2099.82912	
CP= -1.763157895	CP= -1.342105263	CP= -1.052631579	

TABLE III (continued)

## MEASURED SURFACE PRESSURES

25 HZ				67 PER CENT BLADES			
68 TEMP (F)							
ATMOS PRESS (PSF) 2115.7848							
TUNNEL PRESS (PSF) 2106.5796							
TUNNEL Q (PSF) 9.2052							
TUNNEL VELOC (FPS) 88.79568493							
PORT # 1	PORT # 10	PORT # 19		PORT # 20	PORT # 21	PORT # 22	
X/C = 0.352	X/C = 0.64	X/C = 0.832		X/C = 0.848	X/C = 0.864	X/C = 0.88	
PORT PRESS = 2090.62392	PORT PRESS = 2090.62392	PORT PRESS = 2095.12424		PORT PRESS = 2095.73792	PORT PRESS = 2095.73792	PORT PRESS = 2095.94248	
CP = -1.733333333	CP = -1.733333333	CP = -1.244444444		CP = -1.177777778	CP = -1.177777778	CP = -1.155555556	
PORT # 2	PORT # 11	PORT # 20		PORT # 21	PORT # 22	PORT # 23	
X/C = 0.384	X/C = 0.672	X/C = 0.848		X/C = 0.864	X/C = 0.88	X/C = 0.896	
PORT PRESS = 2090.82848	PORT PRESS = 2090.60112	PORT PRESS = 2095.73792		PORT PRESS = 2095.73792	PORT PRESS = 2095.73792	PORT PRESS = 2095.94248	
CP = -1.711111111	CP = -1.844444444	CP = -1.177777778		CP = -1.177777778	CP = -1.177777778	CP = -1.155555556	
PORT # 3	PORT # 12	PORT # 21		PORT # 22	PORT # 23	PORT # 24	
X/C = 0.416	X/C = 0.72	X/C = 0.864		X/C = 0.88	X/C = 0.896	X/C = 0.912	
PORT PRESS = 2091.03304	PORT PRESS = 2091.03304	PORT PRESS = 2095.73792		PORT PRESS = 2095.73792	PORT PRESS = 2095.94248	PORT PRESS = 2096.14704	
CP = -1.688888889	CP = -1.688888889	CP = -1.177777778		CP = -1.177777778	CP = -1.155555556	CP = -1.133333333	
PORT # 4	PORT # 13	PORT # 22		PORT # 23	PORT # 24	PORT # 25	
X/C = 0.448	X/C = 0.736	X/C = 0.88		X/C = 0.896	X/C = 0.912	X/C = 0.928	
PORT PRESS = 2091.2376	PORT PRESS = 2092.2604	PORT PRESS = 2095.73792		PORT PRESS = 2095.94248	PORT PRESS = 2096.14704	PORT PRESS = 2096.3516	
CP = -1.666666667	CP = -1.555555556	CP = -1.177777778		CP = -1.155555556	CP = -1.133333333	CP = -1.111111111	
PORT # 5	PORT # 14	PORT # 23		PORT # 24	PORT # 25	PORT # 26	
X/C = 0.48	X/C = 0.752	X/C = 0.896		X/C = 0.912	X/C = 0.928	X/C = 0.944	
PORT PRESS = 2091.44216	PORT PRESS = 2093.07864	PORT PRESS = 2095.94248		PORT PRESS = 2096.14704	PORT PRESS = 2096.3516	PORT PRESS = 2096.56667	
CP = -1.644444444	CP = -1.466666667	CP = -1.155555556		CP = -1.133333333	CP = -1.111111111	CP = -1.088888889	
PORT # 6	PORT # 15	PORT # 24		PORT # 25	PORT # 26	PORT # 27	
X/C = 0.512	X/C = 0.768	X/C = 0.912		X/C = 0.928	X/C = 0.944	X/C = 0.96	
PORT PRESS = 2091.64672	PORT PRESS = 2093.69232	PORT PRESS = 2096.14704		PORT PRESS = 2096.3516	PORT PRESS = 2096.56667	PORT PRESS = 2096.76672	
CP = -1.622222222	CP = -1.4	CP = -1.133333333		CP = -1.111111111	CP = -1.088888889	CP = -1.066666667	
PORT # 7	PORT # 16	PORT # 25		PORT # 26	PORT # 27	PORT # 28	
X/C = 0.544	X/C = 0.784	X/C = 0.928		X/C = 0.944	X/C = 0.96	X/C = 0.98	
PORT PRESS = 2091.85128	PORT PRESS = 2094.10144	PORT PRESS = 2096.3516		PORT PRESS = 2096.56667	PORT PRESS = 2096.76672	PORT PRESS = 2096.96672	
CP = -1.6	CP = -1.355555556	CP = -1.111111111		CP = -1.088888889	CP = -1.066666667	CP = -1.044444444	
PORT # 8	PORT # 17	PORT # 26		PORT # 27	PORT # 28	PORT # 29	
X/C = 0.576	X/C = 0.8	X/C = 0.944		X/C = 0.96	X/C = 0.98	X/C = 1.0	
PORT PRESS = 2092.2604	PORT PRESS = 2094.71512	PORT PRESS = 2096.76672		PORT PRESS = 2096.96672	PORT PRESS = 2097.16672	PORT PRESS = 2097.36672	
CP = -1.555555556	CP = -1.288888889	CP = -1.066666667		CP = -1.044444444	CP = -1.022222222	CP = -1.0	
PORT # 9	PORT # 18	PORT # 27		PORT # 28	PORT # 29	PORT # 30	
X/C = 0.608	X/C = 0.816	X/C = 0.98		X/C = 1.0	X/C = 1.02	X/C = 1.04	
PORT PRESS = 2091.03304	PORT PRESS = 2094.71512	PORT PRESS = 2096.76672		PORT PRESS = 2096.96672	PORT PRESS = 2097.16672	PORT PRESS = 2097.36672	
CP = -1.688888889	CP = -1.288888889	CP = -1.066666667		CP = -1.044444444	CP = -1.022222222	CP = -1.0	

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BURIES			
30 HZ			
68 TEMP (F)			
ATMOS PRESS (PSF)	2115.7848		
TUNNEL PRESS (PSF)	2105.5568		
TUNNEL Q (PSF)	10.228		
TUNNEL VELOC (FFS)	93.59887025		
PORT # 1	PORT # 10	PORT # 19	
X/C= 0.352	X/C= 0.64	X/C= 0.832	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2094.10144
CP= -1.56	CP= -1.56	CP= -1.12	
PORT # 2	PORT # 11	PORT # 20	
X/C= 0.384	X/C= 0.672	X/C= 0.848	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2094.71512
CP= -1.52	CP= -1.76	CP= -1.06	
PORT # 3	PORT # 12	PORT # 21	
X/C= 0.416	X/C= 0.72	X/C= 0.864	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2094.71512
CP= -1.48	CP= -1.56	CP= -1.06	
PORT # 4	PORT # 13	PORT # 22	
X/C= 0.448	X/C= 0.736	X/C= 0.88	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2094.91968
CP= -1.46	CP= -1.4	CP= -1.04	
PORT # 5	PORT # 14	PORT # 23	
X/C= 0.48	X/C= 0.752	X/C= 0.896	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2094.91968
CP= -1.46	CP= -1.36	CP= -1.04	
PORT # 6	PORT # 15	PORT # 24	
X/C= 0.512	X/C= 0.768	X/C= 0.912	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2095.12424
CP= -1.46	CP= -1.32	CP= -1.02	
PORT # 7	PORT # 16	PORT # 25	
X/C= 0.544	X/C= 0.784	X/C= 0.928	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2095.12424
CP= -1.46	CP= -1.28	CP= -1.02	
PORT # 8	PORT # 17	PORT # 26	
X/C= 0.576	X/C= 0.8	X/C= 0.944	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2095.3288
CP= -1.42	CP= -1.2	CP= -1	
PORT # 9	PORT # 18	PORT # 27	
X/C= 0.608	X/C= 0.816	X/C= 0.96	
PORT PRESS=	PORT PRESS=	PORT PRESS=	2095.73792
CP= -1.56	CP= -1.16	CP= -0.96	

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BLUNDES			
40 HZ			
68 TEMP (F)			
ATHOS PRESS (PSF)	2115.7848		
TUNNEL PRESS (PSF)	2106.5796		
TUNNEL V (FPS)	9.2052		
TUNNEL VELOC (FPS)	88.79568493		
PORT # 1		PORT # 10	PORT # 19
X/C= 0.752		X/C= 0.64	X/C= 0.832
PORT PRESS= 2092.66952		PORT PRESS= 2092.66952	PORT PRESS= 2096.76072
CP= -1.511111111		CP= -1.511111111	CP= -1.056666667
PORT # 2		PORT # 11	PORT # 20
X/C= 0.394		X/C= 0.672	X/C= 0.848
PORT PRESS= 2092.87408		PORT PRESS= 2091.64672	PORT PRESS= 2096.96528
CP= -1.488888889		CP= -1.632222222	CP= -1.044444444
PORT # 3		PORT # 12	PORT # 21
X/C= 0.416		X/C= 0.72	X/C= 0.864
PORT PRESS= 2093.07864		PORT PRESS= 2092.66952	PORT PRESS= 2097.16984
CP= -1.466666667		CP= -1.511111111	CP= -1.022222222
PORT # 4		PORT # 13	PORT # 22
X/C= 0.448		X/C= 0.736	X/C= 0.88
PORT PRESS= 2093.48776		PORT PRESS= 2093.69232	PORT PRESS= 2097.57896
CP= -1.422222222		CP= -1.4	CP= -0.977777778
PORT # 5		PORT # 14	PORT # 23
X/C= 0.48		X/C= 0.752	X/C= 0.896
PORT PRESS= 2093.69232		PORT PRESS= 2094.71512	PORT PRESS= 2097.78352
CP= -1.4		CP= -1.288888889	CP= -0.955555556
PORT # 6		PORT # 15	PORT # 24
X/C= 0.512		X/C= 0.768	X/C= 0.912
PORT PRESS= 2093.69232		PORT PRESS= 2095.12424	PORT PRESS= 2097.78352
CP= -1.4		CP= -1.244444444	CP= -0.955555556
PORT # 7		PORT # 16	PORT # 25
X/C= 0.544		X/C= 0.784	X/C= 0.928
PORT PRESS= 2093.69232		PORT PRESS= 2095.3288	PORT PRESS= 2097.96808
CP= -1.4		CP= -1.222222222	CP= -0.933333333
PORT # 8		PORT # 17	PORT # 26
X/C= 0.576		X/C= 0.8	X/C= 0.944
PORT PRESS= 2094.306		PORT PRESS= 2095.73792	PORT PRESS= 2098.19264
CP= -1.333333333		CP= -1.177777778	CP= -0.911111111
PORT # 9		PORT # 18	PORT # 27
X/C= 0.608		X/C= 0.816	X/C= 0.96
PORT PRESS= 2093.07864		PORT PRESS= 2096.3516	PORT PRESS= 2098.3972
CP= -1.466666667		CP= -1.111111111	CP= -0.888888889



TABLE III (continued)

## MEASURED SURFACE PRESSURES

50 HZ				67 PER CENT BLADES			
68 TEMP (F)							
ATMOS PRESS (PSF) 2115.7848							
TUNNEL PRESS (PSF) 2105.5568							
TUNNEL Q (PSF) 10.228							
TUNNEL VELOC (FPS) 93.59887025							
PORT # 1	PORT # 10	PORT # 19					
X/C= 0.352	X/C= 0.64	X/C= 0.832					
PORT PRESS= 2086.57832	PORT PRESS= 2089.192	PORT PRESS= 2094.51056					
CP= -1.66	CP= -1.6	CP= -1.08					
PORT # 2	PORT # 11	PORT # 20					
X/C= 0.304	X/C= 0.672	X/C= 0.848					
PORT PRESS= 2088.98744	PORT PRESS= 2087.96464	PORT PRESS= 2094.71512					
CP= -1.62	CP= -1.72	CP= -1.06					
PORT # 3	PORT # 12	PORT # 21					
X/C= 0.416	X/C= 0.72	X/C= 0.864					
PORT PRESS= 2089.192	PORT PRESS= 2090.01024	PORT PRESS= 2094.91968					
CP= -1.6	CP= -1.52	CP= -1.04					
PORT # 4	PORT # 13	PORT # 22					
X/C= 0.448	X/C= 0.736	X/C= 0.88					
PORT PRESS= 2089.60112	PORT PRESS= 2091.03304	PORT PRESS= 2095.12424					
CP= -1.56	CP= -1.42	CP= -1.02					
PORT # 5	PORT # 14	PORT # 23					
X/C= 0.49	X/C= 0.752	X/C= 0.896					
PORT PRESS= 2090.01024	PORT PRESS= 2091.64672	PORT PRESS= 2095.3288					
CP= -1.52	CP= -1.36	CP= -1					
PORT # 6	PORT # 15	PORT # 24					
X/C= 0.512	X/C= 0.768	X/C= 0.912					
PORT PRESS= 2090.01024	PORT PRESS= 2092.62352	PORT PRESS= 2095.73792					
CP= -1.52	CP= -1.28	CP= -0.96					
PORT # 7	PORT # 16	PORT # 25					
X/C= 0.544	X/C= 0.784	X/C= 0.928					
PORT PRESS= 2090.01024	PORT PRESS= 2092.87468	PORT PRESS= 2096.14704					
CP= -1.52	CP= -1.24	CP= -0.92					
PORT # 8	PORT # 17	PORT # 26					
X/C= 0.576	X/C= 0.8	X/C= 0.944					
PORT PRESS= 2090.82848	PORT PRESS= 2093.2832	PORT PRESS= 2096.3516					
CP= -1.44	CP= -1.2	CP= -0.9					
PORT # 9	PORT # 18	PORT # 27					
X/C= 0.608	X/C= 0.816	X/C= 0.96					
PORT PRESS= 2089.60112	PORT PRESS= 2093.69232	PORT PRESS= 2096.55616					
CP= -1.56	CP= -1.16	CP= -0.88					

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BLADES		
68 HZ		
69 TEMP (F)		
ATMOS PRESS (PSF)	2115.7848	
TUNNEL PRESS (PSF)	2108.01152	
TUNNEL Q (PSF)	7.77328	
TUNNEL VELOC (FPS)	81.59760333	
PORT # 1		PORT # 10
X/C= 0.352		X/C= 0.64
PORT PRESS= 2094.10144		PORT PRESS= 2094.51056
CP= -1.736947368		CP= -1.736942105
PORT # 2		PORT # 11
X/C= 0.384		X/C= 0.672
PORT PRESS= 2094.51056		PORT PRESS= 2093.2832
CP= -1.736942105		CP= -1.894736842
PORT # 3		PORT # 12
X/C= 0.416		X/C= 0.72
PORT PRESS= 2094.71512		PORT PRESS= 2094.71512
CP= -1.710526316		CP= -1.710526316
PORT # 4		PORT # 13
X/C= 0.448		X/C= 0.756
PORT PRESS= 2094.91968		PORT PRESS= 2095.73792
CP= -1.684210526		CP= -1.578947368
PORT # 5		PORT # 14
X/C= 0.48		X/C= 0.792
PORT PRESS= 2095.12424		PORT PRESS= 2096.55616
CP= -1.657894737		CP= -1.473684211
PORT # 6		PORT # 15
X/C= 0.512		X/C= 0.788
PORT PRESS= 2095.12424		PORT PRESS= 2096.96528
CP= -1.657894737		CP= -1.421052632
PORT # 7		PORT # 16
X/C= 0.544		X/C= 0.784
PORT PRESS= 2095.12424		PORT PRESS= 2097.16984
CP= -1.657894737		CP= -1.394736842
PORT # 8		PORT # 17
X/C= 0.576		X/C= 0.8
PORT PRESS= 2095.73792		PORT PRESS= 2097.3744
CP= -1.578947368		CP= -1.368421053
PORT # 9		PORT # 18
X/C= 0.608		X/C= 0.816
PORT PRESS= 2094.71512		PORT PRESS= 2098.19264
CP= -1.710526316		CP= -1.263157895
		PORT # 19
		X/C= 0.832
		PORT PRESS= 2098.60176
		CP= -1.510526316
		PORT # 20
		X/C= 0.848
		PORT PRESS= 2098.60632
		CP= -1.184210526
		PORT # 21
		X/C= 0.864
		PORT PRESS= 2098.60632
		CP= -1.184210526
		PORT # 22
		X/C= 0.88
		PORT PRESS= 2099.01088
		CP= -1.157894737
		PORT # 23
		X/C= 0.896
		PORT PRESS= 2099.21544
		CP= -1.131578947
		PORT # 24
		X/C= 0.912
		PORT PRESS= 2099.21544
		CP= -1.131578947
		PORT # 25
		X/C= 0.928
		PORT PRESS= 2099.42
		CP= -1.105263158
		PORT # 26
		X/C= 0.944
		PORT PRESS= 2099.42
		CP= -1.105263158
		PORT # 27
		X/C= 0.96
		PORT PRESS= 2099.62912
		CP= -1.052631579

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BLADES			
70 M2			
68 TEMP (F)			
ATMOS PRESS (PSF)	2115.7848		
TUNNEL PRESS (PSF)	2108.81152		
TUNNEL V (PSF)	7.77328		
TUNNEL VELOC (FPS)	81.53768333		
PORT # 1		PORT # 10	PORT # 13
X/C= 0.352		X/C= 0.64	X/C= 0.832
PORT PRESS= 2094.10144		PORT PRESS= 2094.31056	PORT PRESS= 2098.69176
CP= -1.739473634		CP= -1.736842105	CP= -1.10526316
PORT # 2		PORT # 11	PORT # 20
X/C= 0.384		X/C= 0.672	X/C= 0.848
PORT PRESS= 2094.51056		PORT PRESS= 2093.69232	PORT PRESS= 2099.01068
CP= -1.736842105		CP= -1.842105263	CP= -1.157894737
PORT # 3		PORT # 12	PORT # 31
X/C= 0.416		X/C= 0.72	X/C= 0.864
PORT PRESS= 2095.12424		PORT PRESS= 2094.91968	PORT PRESS= 2099.01068
CP= -1.657894737		CP= -1.684210526	CP= -1.157894737
PORT # 4		PORT # 13	PORT # 22
X/C= 0.448		X/C= 0.736	X/C= 0.88
PORT PRESS= 2095.3288		PORT PRESS= 2095.73792	PORT PRESS= 2099.01068
CP= -1.631578947		CP= -1.578947368	CP= -1.157894737
PORT # 5		PORT # 14	PORT # 23
X/C= 0.48		X/C= 0.752	X/C= 0.896
PORT PRESS= 2095.3288		PORT PRESS= 2096.55616	PORT PRESS= 2099.1544
CP= -1.631578947		CP= -1.47368421	CP= -1.131578947
PORT # 6		PORT # 15	PORT # 24
X/C= 0.512		X/C= 0.768	X/C= 0.912
PORT PRESS= 2095.3288		PORT PRESS= 2096.96528	PORT PRESS= 2099.42
CP= -1.631578947		CP= -1.421052632	CP= -1.105263158
PORT # 7		PORT # 16	PORT # 25
X/C= 0.544		X/C= 0.784	X/C= 0.928
PORT PRESS= 2095.3288		PORT PRESS= 2097.3744	PORT PRESS= 2099.42
CP= -1.631578947		CP= -1.368421053	CP= -1.105263158
PORT # 8		PORT # 17	PORT # 26
X/C= 0.576		X/C= 0.8	X/C= 0.944
PORT PRESS= 2096.14704		PORT PRESS= 2097.78352	PORT PRESS= 2099.62456
CP= -1.526315789		CP= -1.315789474	CP= -1.078947368
PORT # 9		PORT # 18	PORT # 27
X/C= 0.598		X/C= 0.816	X/C= 0.96
PORT PRESS= 2094.91968		PORT PRESS= 2098.19264	PORT PRESS= 2099.82912
CP= -1.684210526		CP= -1.263157895	CP= -1.052631579

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BLADES			
80 68 M2 TEMP (F)	2115.7848 2103.92032 11.86448 100.0096684		
ATMOS PRESS (PSF)			
TUNNEL PRESS (PSF)			
TUNNEL O (PSF)			
TUNNEL VELOC (FPS)			
PORT # 1	PORT # 10	PORT # 19	PORT # 28
X/C= 0.352	X/C= 0.64	X/C= 0.832	X/C= 0.832
PORT PRESS= 2088.37376	PORT PRESS= 2087.96464	PORT PRESS= 2092.05584	PORT PRESS= 2092.05584
CP= -1.310344828	CP= -1.344327586	CP= -1	CP= -1
PORT # 2	PORT # 11	PORT # 20	
X/C= 0.384	X/C= 0.672	X/C= 0.848	
PORT PRESS= 2088.78288	PORT PRESS= 2086.32816	PORT PRESS= 2092.46496	
CP= -1.275862069	CP= -1.48275862	CP= -0.965517241	
PORT # 3	PORT # 12	PORT # 21	
X/C= 0.416	X/C= 0.72	X/C= 0.864	
PORT PRESS= 2089.192	PORT PRESS= 2087.55552	PORT PRESS= 2092.46496	
CP= -1.24137931	CP= -1.379310345	CP= -0.965517241	
PORT # 4	PORT # 13	PORT # 22	
X/C= 0.448	X/C= 0.736	X/C= 0.88	
PORT PRESS= 2089.60112	PORT PRESS= 2088.98744	PORT PRESS= 2092.66952	
CP= -1.206896552	CP= -1.258620630	CP= -0.946275862	
PORT # 5	PORT # 14	PORT # 23	
X/C= 0.48	X/C= 0.752	X/C= 0.896	
PORT PRESS= 2089.60112	PORT PRESS= 2089.60112	PORT PRESS= 2092.87408	
CP= -1.206896552	CP= -1.206896552	CP= -0.931034483	
PORT # 6	PORT # 15	PORT # 24	
X/C= 0.512	X/C= 0.768	X/C= 0.912	
PORT PRESS= 2089.60112	PORT PRESS= 2090.01024	PORT PRESS= 2093.07864	
CP= -1.206896552	CP= -1.172413793	CP= -0.913793103	
PORT # 7	PORT # 16	PORT # 25	
X/C= 0.544	X/C= 0.784	X/C= 0.938	
PORT PRESS= 2089.60112	PORT PRESS= 2090.41936	PORT PRESS= 2093.2832	
CP= -1.206896552	CP= -1.137931034	CP= -0.896551724	
PORT # 8	PORT # 17	PORT # 26	
X/C= 0.576	X/C= 0.8	X/C= 0.944	
PORT PRESS= 2090.01024	PORT PRESS= 2091.03304	PORT PRESS= 2093.2832	
CP= -1.172413793	CP= -1.086206897	CP= -0.896551724	
PORT # 9	PORT # 18	PORT # 27	
X/C= 0.608	X/C= 0.816	X/C= 0.96	
PORT PRESS= 2088.37376	PORT PRESS= 2091.44216	PORT PRESS= 2093.69232	
CP= -1.310344828	CP= -1.051724138	CP= -0.862068966	

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BLADES			
96 MZ			
68 TEMP (F)			
ATMOS PRESS (PSF)	2115.7848		
TUNNEL PRESS (PSF)	2106.5796		
TUNNEL Q (PSF)	9.2052		
TUNNEL VELOC (FPS)	88.79568493		
PORT # 1		PORT # 10	PORT # 19
X/C= 0.352		X/C= 0.64	X/C= 0.832
PORT PRESS= 2092.2604		PORT PRESS= 2092.66952	PORT PRESS= 2096.76072
CP= -1.53555556		CP= -1.51111111	CP= -1.06666667
PORT # 2		PORT # 11	PORT # 20
X/C= 0.384		X/C= 0.672	X/C= 0.848
PORT PRESS= 2092.66952		PORT PRESS= 2091.44216	PORT PRESS= 2097.16984
CP= -1.51111111		CP= -1.64444444	CP= -1.02222222
PORT # 3		PORT # 12	PORT # 21
X/C= 0.416		X/C= 0.72	X/C= 0.864
PORT PRESS= 2093.07864		PORT PRESS= 2093.07864	PORT PRESS= 2097.16984
CP= -1.46666667		CP= -1.46666667	CP= -1.02222222
PORT # 4		PORT # 13	PORT # 22
X/C= 0.448		X/C= 0.736	X/C= 0.88
PORT PRESS= 2093.2832		PORT PRESS= 2094.10144	PORT PRESS= 2097.57896
CP= -1.44444444		CP= -1.35555556	CP= -0.97777778
PORT # 5		PORT # 14	PORT # 23
X/C= 0.48		X/C= 0.752	X/C= 0.896
PORT PRESS= 2093.69232		PORT PRESS= 2094.71512	PORT PRESS= 2097.57896
CP= -1.4		CP= -1.28888889	CP= -0.97777778
PORT # 6		PORT # 15	PORT # 24
X/C= 0.512		X/C= 0.768	X/C= 0.912
PORT PRESS= 2093.48776		PORT PRESS= 2095.12424	PORT PRESS= 2097.57896
CP= -1.42222222		CP= -1.24444444	CP= -0.97777778
PORT # 7		PORT # 16	PORT # 25
X/C= 0.544		X/C= 0.784	X/C= 0.938
PORT PRESS= 2093.48776		PORT PRESS= 2095.53336	PORT PRESS= 2097.78352
CP= -1.42222222		CP= -1.2	CP= -0.95555556
PORT # 8		PORT # 17	PORT # 26
X/C= 0.576		X/C= 0.8	X/C= 0.944
PORT PRESS= 2093.89688		PORT PRESS= 2095.94248	PORT PRESS= 2097.96808
CP= -1.37777778		CP= -1.15555556	CP= -0.93333333
PORT # 9		PORT # 18	PORT # 27
X/C= 0.608		X/C= 0.816	X/C= 0.96
PORT PRESS= 2092.66952		PORT PRESS= 2096.3516	PORT PRESS= 2098.3972
CP= -1.51111111		CP= -1.11111111	CP= -0.88888889

TABLE III (continued)

## MEASURED SURFACE PRESSURES

67 PER CENT BLADES			
100 MZ			
68 TEMP (F)			
ATHOS PRESS (PSF) 2115.7848			
TUNNEL PRESS (PSF) 2108.01152			
TUNNEL Q (PSF) 7.77328			
TUNNEL VELOC (FPS) 81.59760333			
PORT # 1	PORT # 10	PORT # 19	
X/C= 0.352	X/C= 0.64	X/C= 0.822	
PORT PRESS= 2094.10144	PORT PRESS= 2094.51056	PORT PRESS= 2099.60176	
CP= -1.789473684	CP= -1.736842105	CP= -1.1210526316	
PORT # 2	PORT # 11	PORT # 20	
X/C= 0.384	X/C= 0.672	X/C= 0.846	
PORT PRESS= 2094.51056	PORT PRESS= 2093.63232	PORT PRESS= 2099.01088	
CP= -1.736842105	CP= -1.842105263	CP= -1.157894737	
PORT # 3	PORT # 12	PORT # 21	
X/C= 0.416	X/C= 0.72	X/C= 0.864	
PORT PRESS= 2094.71512	PORT PRESS= 2094.91968	PORT PRESS= 2099.01088	
CP= -1.710526316	CP= -1.684210526	CP= -1.157894737	
PORT # 4	PORT # 13	PORT # 22	
X/C= 0.448	X/C= 0.736	X/C= 0.88	
PORT PRESS= 2094.91968	PORT PRESS= 2095.94248	PORT PRESS= 2094.21544	
CP= -1.634210526	CP= -1.552631579	CP= -1.131578947	
PORT # 5	PORT # 14	PORT # 23	
X/C= 0.48	X/C= 0.752	X/C= 0.896	
PORT PRESS= 2095.3208	PORT PRESS= 2096.3516	PORT PRESS= 2099.21544	
CP= -1.631578947	CP= -1.5	CP= -1.131578947	
PORT # 6	PORT # 15	PORT # 24	
X/C= 0.512	X/C= 0.768	X/C= 0.912	
PORT PRESS= 2095.12424	PORT PRESS= 2096.96528	PORT PRESS= 2099.42	
CP= -1.657894737	CP= -1.421052632	CP= -1.105263158	
PORT # 7	PORT # 16	PORT # 25	
X/C= 0.544	X/C= 0.784	X/C= 0.936	
PORT PRESS= 2095.12424	PORT PRESS= 2097.16984	PORT PRESS= 2099.62456	
CP= -1.657894737	CP= -1.394736842	CP= -1.078947368	
PORT # 8	PORT # 17	PORT # 26	
X/C= 0.576	X/C= 0.8	X/C= 0.944	
PORT PRESS= 2095.73792	PORT PRESS= 2097.78352	PORT PRESS= 2099.62456	
CP= -1.578947368	CP= -1.315789474	CP= -1.078947368	
PORT # 9	PORT # 18	PORT # 27	
X/C= 0.608	X/C= 0.816	X/C= 0.96	
PORT PRESS= 2094.71512	PORT PRESS= 2098.19264	PORT PRESS= 2099.62412	
CP= -1.710526316	CP= -1.263157895	CP= -1.052631579	

TABLE III (continued)

## MEASURED SURFACE PRESSURES

2 MZ			98 PER CENT BLURIES		
72 TEMP (F)					
TUNNEL PRESS (PSF) 2121.426893					
TUNNEL PRESS (PSF) 2117.335693					
TUNNEL Q (PSF) 4.8912					
TUNNEL VELOC (FPS) 59.34186193					
PORT # 1	PORT # 10	PORT # 19			
X/C= 0.352	X/C= 0.64	X/C= 0.832			
PORT PRESS= 2109.153293	PORT PRESS= 2109.971533	PORT PRESS= 2111.812573			
CP= -2	CP= -1.8	CP= -1.35			
PORT # 2	PORT # 11	PORT # 20			
X/C= 0.384	X/C= 0.672	X/C= 0.848			
PORT PRESS= 2109.357853	PORT PRESS= 2109.153293	PORT PRESS= 2112.221693			
CP= -1.95	CP= -2	CP= -1.25			
PORT # 3	PORT # 12	PORT # 21			
X/C= 0.416	X/C= 0.72	X/C= 0.864			
PORT PRESS= 2109.766973	PORT PRESS= 2109.971533	PORT PRESS= 2112.221693			
CP= -1.85	CP= -1.8	CP= -1.25			
PORT # 4	PORT # 13	PORT # 22			
X/C= 0.448	X/C= 0.736	X/C= 0.88			
PORT PRESS= 2110.176893	PORT PRESS= 2110.585213	PORT PRESS= 2112.630813			
CP= -1.75	CP= -1.65	CP= -1.15			
PORT # 5	PORT # 14	PORT # 23			
X/C= 0.48	X/C= 0.752	X/C= 0.896			
PORT PRESS= 2110.176893	PORT PRESS= 2110.789773	PORT PRESS= 2112.630813			
CP= -1.75	CP= -1.6	CP= -1.15			
PORT # 6	PORT # 15	PORT # 24			
X/C= 0.512	X/C= 0.768	X/C= 0.912			
PORT PRESS= 2110.176893	PORT PRESS= 2111.198893	PORT PRESS= 2112.630813			
CP= -1.75	CP= -1.5	CP= -1.15			
PORT # 7	PORT # 16	PORT # 25			
X/C= 0.544	X/C= 0.784	X/C= 0.928			
PORT PRESS= 2110.176893	PORT PRESS= 2111.403453	PORT PRESS= 2113.039933			
CP= -1.75	CP= -1.45	CP= -1.05			
PORT # 8	PORT # 17	PORT # 26			
X/C= 0.576	X/C= 0.8	X/C= 0.944			
PORT PRESS= 2110.585213	PORT PRESS= 2111.403453	PORT PRESS= 2113.039933			
CP= -1.65	CP= -1.45	CP= -1.05			
PORT # 9	PORT # 18	PORT # 27			
X/C= 0.608	X/C= 0.816	X/C= 0.96			
PORT PRESS= 2109.971533	PORT PRESS= 2111.812573	PORT PRESS= 2113.244493			
CP= -1.8	CP= -1.35	CP= -1			

TABLE III (continued)

## MEASURED SURFACE PRESSURES

4 HZ			98 PER CENT BLADES		
72 TEMP (F)					
ATMOS PRESS (PSF) 2121.426893					
TUNNEL PRESS (PSF) 2120.404093					
TUNNEL Q (PSF) 1.0228					
TUNNEL VELOC (FPS) 25.67093096					
PORT # 1	PORT # 10	PORT # 19			
X/C= 0.352	X/C= 0.64	X/C= 0.832			
PORT PRESS= 2119.790413	PORT PRESS= 2118.358493	PORT PRESS= 2119.381293			
CP= -2.6	CP= -2	CP= -1			
PORT # 2	PORT # 11	PORT # 20			
X/C= 0.384	X/C= 0.672	X/C= 0.848			
PORT PRESS= 2117.949373	PORT PRESS= 2118.358493	PORT PRESS= 2119.790413			
CP= -2.4	CP= -2	CP= -0.6			
PORT # 3	PORT # 12	PORT # 21			
X/C= 0.416	X/C= 0.72	X/C= 0.864			
PORT PRESS= 2116.153933	PORT PRESS= 2118.563053	PORT PRESS= 2119.790413			
CP= -2.2	CP= -1.8	CP= -0.6			
PORT # 4	PORT # 13	PORT # 22			
X/C= 0.448	X/C= 0.736	X/C= 0.88			
PORT PRESS= 2118.358493	PORT PRESS= 2118.767613	PORT PRESS= 2119.790413			
CP= -2	CP= -1.4	CP= -0.6			
PORT # 5	PORT # 14	PORT # 23			
X/C= 0.48	X/C= 0.752	X/C= 0.896			
PORT PRESS= 2118.358493	PORT PRESS= 2119.176733	PORT PRESS= 2119.994973			
CP= -2	CP= -1.2	CP= -0.4			
PORT # 6	PORT # 15	PORT # 24			
X/C= 0.512	X/C= 0.768	X/C= 0.912			
PORT PRESS= 2118.358493	PORT PRESS= 2119.176733	PORT PRESS= 2119.994973			
CP= -2	CP= -1.2	CP= -0.4			
PORT # 7	PORT # 16	PORT # 25			
X/C= 0.544	X/C= 0.784	X/C= 0.928			
PORT PRESS= 2118.358493	PORT PRESS= 2119.381293	PORT PRESS= 2119.994973			
CP= -2	CP= -1	CP= -0.4			
PORT # 8	PORT # 17	PORT # 26			
X/C= 0.576	X/C= 0.8	X/C= 0.944			
PORT PRESS= 2118.358493	PORT PRESS= 2119.381293	PORT PRESS= 2119.994973			
CP= -2	CP= -1	CP= -0.4			
PORT # 9	PORT # 18	PORT # 27			
X/C= 0.608	X/C= 0.816	X/C= 0.96			
PORT PRESS= 2118.358493	PORT PRESS= 2118.972173	PORT PRESS= 2120.199533			
CP= -2	CP= -1.4	CP= -0.2			



TABLE III (continued)

## MEASURED SURFACE PRESSURES

98 PER CENT BLADES			
6	NZ		
72	TEMP (F)		
ATMOS PRESS (PSF) 2121.426893			
TUNNEL PRESS (PSF) 2120.404093			
TUNNEL Q (PSF) 1.0228			
TUNNEL VELOC (FPS) 29.67093096			
PORT # 1	PORT # 10	PORT # 19	
X/C= 0.352	X/C= 0.64	X/C= 0.932	
PORT PRESS= 2118.972173	PORT PRESS= 2119.381293	PORT PRESS= 2120.404093	
CP= -1.4	CP= -1	CP= 0	
PORT # 2	PORT # 11	PORT # 20	
X/C= 0.384	X/C= 0.672	X/C= 0.848	
PORT PRESS= 2119.176733	PORT PRESS= 2119.381293	PORT PRESS= 2120.404093	
CP= -1.2	CP= -1	CP= 0	
PORT # 3	PORT # 12	PORT # 21	
X/C= 0.416	X/C= 0.72	X/C= 0.964	
PORT PRESS= 2119.381293	PORT PRESS= 2119.381293	PORT PRESS= 2120.404093	
CP= -1	CP= -1	CP= 0	
PORT # 4	PORT # 13	PORT # 22	
X/C= 0.448	X/C= 0.736	X/C= 0.988	
PORT PRESS= 2119.381293	PORT PRESS= 2119.790413	PORT PRESS= 2120.608653	
CP= -1	CP= -0.6	CP= 0.2	
PORT # 5	PORT # 14	PORT # 23	
X/C= 0.48	X/C= 0.752	X/C= 0.996	
PORT PRESS= 2119.381293	PORT PRESS= 2119.790413	PORT PRESS= 2120.608653	
CP= -1	CP= -0.6	CP= 0.2	
PORT # 6	PORT # 15	PORT # 24	
X/C= 0.512	X/C= 0.768	X/C= 0.912	
PORT PRESS= 2119.381293	PORT PRESS= 2119.790413	PORT PRESS= 2120.608653	
CP= -1	CP= -0.6	CP= 0.2	
PORT # 7	PORT # 16	PORT # 25	
X/C= 0.544	X/C= 0.784	X/C= 0.928	
PORT PRESS= 2119.381293	PORT PRESS= 2119.790413	PORT PRESS= 2120.608653	
CP= -1	CP= -0.6	CP= 0.2	
PORT # 8	PORT # 17	PORT # 26	
X/C= 0.576	X/C= 0.8	X/C= 0.944	
PORT PRESS= 2119.381293	PORT PRESS= 2119.790413	PORT PRESS= 2120.813213	
CP= -1	CP= -0.6	CP= 0.4	
PORT # 9	PORT # 18	PORT # 27	
X/C= 0.608	X/C= 0.816	X/C= 0.96	
PORT PRESS= 2119.381293	PORT PRESS= 2119.381293	PORT PRESS= 2120.813213	
CP= -1	CP= -1	CP= 0.4	

TABLE III (continued)

## MEASURED SURFACE PRESSURES

25 HZ 65 TEMP (F)				98 PER CENT BLUIDS			
ATMOS PRESS (PSF) 2120.016370							
TUNNEL PRESS (PSF) 2117.970770							
TUNNEL Q (PSF) 2.0456							
TUNNEL VELOC (FPS) 41.69792408							
PORT # 1	PORT # 10	PORT # 19					
X/C= 0.352	X/C= 0.64	X/C= 0.832					
PORT PRESS= 2114.902370	PORT PRESS= 2114.902370	PORT PRESS= 2115.516050					
CP= -1.5	CP= -1.5	CP= -1.2					
PORT # 2	PORT # 11	PORT # 20					
X/C= 0.384	X/C= 0.672	X/C= 0.848					
PORT PRESS= 2114.902370	PORT PRESS= 2113.879570	PORT PRESS= 2115.925170					
CP= -1.5	CP= -2	CP= -1					
PORT # 3	PORT # 12	PORT # 21					
X/C= 0.416	X/C= 0.72	X/C= 0.864					
PORT PRESS= 2114.902370	PORT PRESS= 2114.837810	PORT PRESS= 2115.925170					
CP= -1.5	CP= -1.6	CP= -1					
PORT # 4	PORT # 13	PORT # 22					
X/C= 0.448	X/C= 0.736	X/C= 0.88					
PORT PRESS= 2114.902370	PORT PRESS= 2114.902370	PORT PRESS= 2115.925170					
CP= -1.5	CP= -1.5	CP= -1					
PORT # 5	PORT # 14	PORT # 23					
X/C= 0.48	X/C= 0.752	X/C= 0.896					
PORT PRESS= 2114.902370	PORT PRESS= 2115.186930	PORT PRESS= 2116.129730					
CP= -1.5	CP= -1.4	CP= -0.9					
PORT # 6	PORT # 15	PORT # 24					
X/C= 0.512	X/C= 0.768	X/C= 0.912					
PORT PRESS= 2114.902370	PORT PRESS= 2115.516050	PORT PRESS= 2116.129730					
CP= -1.5	CP= -1.2	CP= -0.9					
PORT # 7	PORT # 16	PORT # 25					
X/C= 0.544	X/C= 0.784	X/C= 0.928					
PORT PRESS= 2114.902370	PORT PRESS= 2115.516050	PORT PRESS= 2116.129730					
CP= -1.5	CP= -1.2	CP= -0.9					
PORT # 8	PORT # 17	PORT # 26					
X/C= 0.576	X/C= 0.8	X/C= 0.944					
PORT PRESS= 2114.902370	PORT PRESS= 2115.516050	PORT PRESS= 2116.129730					
CP= -1.5	CP= -1.2	CP= -0.9					
PORT # 9	PORT # 18	PORT # 27					
X/C= 0.608	X/C= 0.816	X/C= 0.96					
PORT PRESS= 2114.902370	PORT PRESS= 2115.516050	PORT PRESS= 2116.334290					
CP= -1.5	CP= -1.2	CP= -0.8					

TABLE III (continued)

## MEASURED SURFACE PRESSURES

30 HZ 65 TEMP (F)				98 PER CENT BLADES			
ATMOS PRESS (PSF) 2120.016370							
TUNNEL PRESS (PSF) 2115.925170							
TUNNEL VEL (FPS) 4.0912							
TUNNEL VELOC (FPS) 58.96976976							
PORT # 1	PORT # 10	PORT # 19					
X/C = 0.352	X/C = 0.64	X/C = 0.832					
PORT PRESS = 2112.856770	PORT PRESS = 2112.856770	PORT PRESS = 2113.265890					
CP = -0.75	CP = -0.75	CP = -0.65					
PORT # 2	PORT # 11	PORT # 20					
X/C = 0.384	X/C = 0.672	X/C = 0.848					
PORT PRESS = 2112.856770	PORT PRESS = 2112.856770	PORT PRESS = 2113.470450					
CP = -0.75	CP = -0.75	CP = -0.6					
PORT # 3	PORT # 12	PORT # 21					
X/C = 0.416	X/C = 0.72	X/C = 0.864					
PORT PRESS = 2112.856770	PORT PRESS = 2112.856770	PORT PRESS = 2113.470450					
CP = -0.75	CP = -0.75	CP = -0.6					
PORT # 4	PORT # 13	PORT # 22					
X/C = 0.448	X/C = 0.736	X/C = 0.88					
PORT PRESS = 2112.856770	PORT PRESS = 2113.061330	PORT PRESS = 2113.470450					
CP = -0.75	CP = -0.7	CP = -0.6					
PORT # 5	PORT # 14	PORT # 23					
X/C = 0.48	X/C = 0.752	X/C = 0.896					
PORT PRESS = 2112.856770	PORT PRESS = 2113.061330	PORT PRESS = 2113.470450					
CP = -0.75	CP = -0.7	CP = -0.6					
PORT # 6	PORT # 15	PORT # 24					
X/C = 0.512	X/C = 0.768	X/C = 0.912					
PORT PRESS = 2112.856770	PORT PRESS = 2113.061330	PORT PRESS = 2113.470450					
CP = -0.75	CP = -0.7	CP = -0.6					
PORT # 7	PORT # 16	PORT # 25					
X/C = 0.544	X/C = 0.784	X/C = 0.928					
PORT PRESS = 2112.856770	PORT PRESS = 2113.265890	PORT PRESS = 2113.470450					
CP = -0.75	CP = -0.65	CP = -0.6					
PORT # 8	PORT # 17	PORT # 26					
X/C = 0.576	X/C = 0.8	X/C = 0.944					
PORT PRESS = 2112.856770	PORT PRESS = 2113.265890	PORT PRESS = 2113.470450					
CP = -0.75	CP = -0.65	CP = -0.6					
PORT # 9	PORT # 18	PORT # 27					
X/C = 0.608	X/C = 0.816	X/C = 0.96					
PORT PRESS = 2112.856770	PORT PRESS = 2113.265890	PORT PRESS = 2113.470450					
CP = -0.75	CP = -0.65	CP = -0.6					

TABLE III (continued)

## MEASURED SURFACE PRESSURES

40 HZ				98 PER CENT BLADES			
CS TEMP (F)							
ATMOS PRESS (PSF) 2120.016370							
TUNNEL PRESS (PSF) 2115.925170							
TUNNEL Q (PSF) 4.0912							
TUNNEL VELOC (FPS) 58.96976976							
PORT # 1	PORT # 10	PORT # 19					
X/C= 0.352	X/C= 0.64	X/C= 0.832					
PORT PRESS= 2113.470450	PORT PRESS= 2113.470450	PORT PRESS= 2113.470450					
CP= -0.6	CP= -0.6	CP= -0.6					
PORT # 2	PORT # 11	PORT # 20					
X/C= 0.384	X/C= 0.672	X/C= 0.848					
PORT PRESS= 2113.470450	PORT PRESS= 2113.061330	PORT PRESS= 2113.470450					
CP= -0.6	CP= -0.7	CP= -0.6					
PORT # 3	PORT # 12	PORT # 21					
X/C= 0.416	X/C= 0.72	X/C= 0.864					
PORT PRESS= 2113.470450	PORT PRESS= 2113.265890	PORT PRESS= 2113.470450					
CP= -0.6	CP= -0.65	CP= -0.6					
PORT # 4	PORT # 13	PORT # 22					
X/C= 0.448	X/C= 0.736	X/C= 0.88					
PORT PRESS= 2113.470450	PORT PRESS= 2113.470450	PORT PRESS= 2113.470450					
CP= -0.6	CP= -0.6	CP= -0.6					
PORT # 5	PORT # 14	PORT # 23					
X/C= 0.48	X/C= 0.752	X/C= 0.896					
PORT PRESS= 2113.470450	PORT PRESS= 2113.470450	PORT PRESS= 2113.470450					
CP= -0.6	CP= -0.6	CP= -0.6					
PORT # 6	PORT # 15	PORT # 24					
X/C= 0.512	X/C= 0.768	X/C= 0.912					
PORT PRESS= 2113.470450	PORT PRESS= 2113.470450	PORT PRESS= 2113.675010					
CP= -0.6	CP= -0.6	CP= -0.55					
PORT # 7	PORT # 16	PORT # 25					
X/C= 0.544	X/C= 0.784	X/C= 0.928					
PORT PRESS= 2113.470450	PORT PRESS= 2113.675010	PORT PRESS= 2113.675010					
CP= -0.6	CP= -0.55	CP= -0.55					
PORT # 8	PORT # 17	PORT # 26					
X/C= 0.576	X/C= 0.8	X/C= 0.944					
PORT PRESS= 2113.470450	PORT PRESS= 2113.675010	PORT PRESS= 2113.675010					
CP= -0.6	CP= -0.55	CP= -0.55					
PORT # 9	PORT # 18	PORT # 27					
X/C= 0.608	X/C= 0.816	X/C= 0.96					
PORT PRESS= 2113.470450	PORT PRESS= 2113.470450	PORT PRESS= 2113.675010					
CP= -0.6	CP= -0.6	CP= -0.55					

TABLE III (continued)

## MEASURED SURFACE PRESSURES

50 HZ				98 PER CENT BLIJES			
55 TEMP (F)							
ATHOS PRESS (PSF) 2120.016370							
TUNNEL PRESS (PSF) 2115.516050							
TUNNEL O. (PSF) 4.50032							
TUNNEL VELOC (FPS) 61.84801630							
PORT # 1	PORT # 10	PORT # 19		PORT # 10	PORT # 19		
X/C= 0.352	X/C= 0.64	X/C= 0.832		X/C= 0.64	X/C= 0.832		
PORT PRESS= 2110.402050	PORT PRESS= 2111.015730	PORT PRESS= 2112.243090		PORT PRESS= 2111.015730	PORT PRESS= 2112.243090		
CP= -1.136363636	CP= -1	CP= -0.727272727		CP= -1	CP= -0.727272727		
PORT # 2	PORT # 11	PORT # 20		PORT # 11	PORT # 20		
X/C= 0.384	X/C= 0.672	X/C= 0.848		X/C= 0.672	X/C= 0.848		
PORT PRESS= 2110.402050	PORT PRESS= 2110.402050	PORT PRESS= 2112.447650		PORT PRESS= 2110.402050	PORT PRESS= 2112.447650		
CP= -1.136363636	CP= -1.136363636	CP= -0.681818182		CP= -1.136363636	CP= -0.681818182		
PORT # 3	PORT # 12	PORT # 21		PORT # 12	PORT # 21		
X/C= 0.416	X/C= 0.72	X/C= 0.864		X/C= 0.72	X/C= 0.864		
PORT PRESS= 2110.606610	PORT PRESS= 2111.015730	PORT PRESS= 2112.447650		PORT PRESS= 2111.015730	PORT PRESS= 2112.447650		
CP= -1.090909090	CP= -1	CP= -0.681818182		CP= -1	CP= -0.681818182		
PORT # 4	PORT # 13	PORT # 22		PORT # 13	PORT # 22		
X/C= 0.448	X/C= 0.736	X/C= 0.88		X/C= 0.736	X/C= 0.88		
PORT PRESS= 2110.606610	PORT PRESS= 2111.424850	PORT PRESS= 2112.447650		PORT PRESS= 2111.424850	PORT PRESS= 2112.447650		
CP= -1.040909090	CP= -0.909090909	CP= -0.681818182		CP= -0.909090909	CP= -0.681818182		
PORT # 5	PORT # 14	PORT # 23		PORT # 14	PORT # 23		
X/C= 0.48	X/C= 0.752	X/C= 0.896		X/C= 0.752	X/C= 0.896		
PORT PRESS= 2110.606610	PORT PRESS= 2111.424850	PORT PRESS= 2112.652210		PORT PRESS= 2111.424850	PORT PRESS= 2112.652210		
CP= -1.030909090	CP= -0.909090909	CP= -0.636363636		CP= -0.909090909	CP= -0.636363636		
PORT # 6	PORT # 15	PORT # 24		PORT # 15	PORT # 24		
X/C= 0.512	X/C= 0.768	X/C= 0.912		X/C= 0.768	X/C= 0.912		
PORT PRESS= 2110.606610	PORT PRESS= 2111.833970	PORT PRESS= 2112.856770		PORT PRESS= 2111.833970	PORT PRESS= 2112.856770		
CP= -1.030909090	CP= -0.818181818	CP= -0.590909090		CP= -0.818181818	CP= -0.590909090		
PORT # 7	PORT # 16	PORT # 25		PORT # 16	PORT # 25		
X/C= 0.544	X/C= 0.784	X/C= 0.928		X/C= 0.784	X/C= 0.928		
PORT PRESS= 2110.606610	PORT PRESS= 2111.833970	PORT PRESS= 2113.061330		PORT PRESS= 2111.833970	PORT PRESS= 2113.061330		
CP= -1.030909090	CP= -0.818181818	CP= -0.545454545		CP= -0.818181818	CP= -0.545454545		
PORT # 8	PORT # 17	PORT # 26		PORT # 17	PORT # 26		
X/C= 0.576	X/C= 0.8	X/C= 0.944		X/C= 0.8	X/C= 0.944		
PORT PRESS= 2110.606610	PORT PRESS= 2112.038530	PORT PRESS= 2113.265890		PORT PRESS= 2112.038530	PORT PRESS= 2113.265890		
CP= -1.030909090	CP= -0.772727273	CP= -0.5		CP= -0.772727273	CP= -0.5		
PORT # 9	PORT # 18	PORT # 27		PORT # 18	PORT # 27		
X/C= 0.608	X/C= 0.816	X/C= 0.96		X/C= 0.816	X/C= 0.96		
PORT PRESS= 2110.606610	PORT PRESS= 2112.038530	PORT PRESS= 2113.470450		PORT PRESS= 2112.038530	PORT PRESS= 2113.470450		
CP= -1.090909090	CP= -0.772727273	CP= -0.454545455		CP= -0.772727273	CP= -0.454545455		

TABLE III (continued)

## MEASURED SURFACE PRESSURES

60 HZ 55 TEMP (F) ATMOS PRESS (PSF) 2120.016370 TUNNEL PRESS (PSF) 2117.970770 TUNNEL Q (PSF) 2.0456 TUNNEL VELOC (FPS) 41.69792408				90 PER CENT BLADES			
PORT # 1 X/C= 0.352 PORT PRESS= 2115.925170 CP= -1	PORT # 10 X/C= 0.64 PORT PRESS= 2115.925170 CP= -1	PORT # 19 X/C= 0.832 PORT PRESS= 2116.538850 CP= -0.7	PORT # 28 X/C= 0.843 PORT PRESS= 2116.538850 CP= -0.7	PORT # 37 X/C= 0.864 PORT PRESS= 2116.538850 CP= -0.7	PORT # 46 X/C= 0.876 PORT PRESS= 2116.743410 CP= -0.6	PORT # 55 X/C= 0.888 PORT PRESS= 2116.743410 CP= -0.6	PORT # 64 X/C= 0.899 PORT PRESS= 2116.743410 CP= -0.6
PORT # 2 X/C= 0.384 PORT PRESS= 2115.925170 CP= -1	PORT # 11 X/C= 0.672 PORT PRESS= 2115.925170 CP= -1	PORT # 20 X/C= 0.843 PORT PRESS= 2116.538850 CP= -0.7	PORT # 29 X/C= 0.864 PORT PRESS= 2116.538850 CP= -0.7	PORT # 38 X/C= 0.876 PORT PRESS= 2116.743410 CP= -0.6	PORT # 47 X/C= 0.888 PORT PRESS= 2116.743410 CP= -0.6	PORT # 56 X/C= 0.899 PORT PRESS= 2116.743410 CP= -0.6	PORT # 65 X/C= 0.910 PORT PRESS= 2116.947970 CP= -0.5
PORT # 3 X/C= 0.416 PORT PRESS= 2115.925170 CP= -1	PORT # 12 X/C= 0.72 PORT PRESS= 2116.129730 CP= -0.9	PORT # 21 X/C= 0.864 PORT PRESS= 2116.538850 CP= -0.7	PORT # 30 X/C= 0.885 PORT PRESS= 2116.743410 CP= -0.6	PORT # 39 X/C= 0.896 PORT PRESS= 2116.743410 CP= -0.6	PORT # 48 X/C= 0.907 PORT PRESS= 2116.743410 CP= -0.6	PORT # 57 X/C= 0.918 PORT PRESS= 2116.947970 CP= -0.5	PORT # 66 X/C= 0.929 PORT PRESS= 2116.947970 CP= -0.5
PORT # 4 X/C= 0.448 PORT PRESS= 2115.925170 CP= -1	PORT # 13 X/C= 0.736 PORT PRESS= 2116.129730 CP= -0.9	PORT # 22 X/C= 0.876 PORT PRESS= 2116.538850 CP= -0.7	PORT # 31 X/C= 0.897 PORT PRESS= 2116.743410 CP= -0.6	PORT # 40 X/C= 0.908 PORT PRESS= 2116.743410 CP= -0.6	PORT # 49 X/C= 0.919 PORT PRESS= 2116.947970 CP= -0.5	PORT # 58 X/C= 0.930 PORT PRESS= 2116.947970 CP= -0.5	PORT # 67 X/C= 0.941 PORT PRESS= 2116.947970 CP= -0.5
PORT # 5 X/C= 0.48 PORT PRESS= 2115.925170 CP= -1	PORT # 14 X/C= 0.752 PORT PRESS= 2116.129730 CP= -0.9	PORT # 23 X/C= 0.885 PORT PRESS= 2116.538850 CP= -0.7	PORT # 32 X/C= 0.906 PORT PRESS= 2116.743410 CP= -0.6	PORT # 41 X/C= 0.917 PORT PRESS= 2116.743410 CP= -0.6	PORT # 50 X/C= 0.928 PORT PRESS= 2116.947970 CP= -0.5	PORT # 59 X/C= 0.939 PORT PRESS= 2116.947970 CP= -0.5	PORT # 68 X/C= 0.950 PORT PRESS= 2116.947970 CP= -0.5
PORT # 6 X/C= 0.512 PORT PRESS= 2115.925170 CP= -1	PORT # 15 X/C= 0.768 PORT PRESS= 2116.129730 CP= -0.9	PORT # 24 X/C= 0.896 PORT PRESS= 2116.538850 CP= -0.7	PORT # 33 X/C= 0.917 PORT PRESS= 2116.743410 CP= -0.6	PORT # 42 X/C= 0.928 PORT PRESS= 2116.743410 CP= -0.6	PORT # 51 X/C= 0.939 PORT PRESS= 2116.947970 CP= -0.5	PORT # 60 X/C= 0.950 PORT PRESS= 2116.947970 CP= -0.5	PORT # 69 X/C= 0.961 PORT PRESS= 2116.947970 CP= -0.5
PORT # 7 X/C= 0.544 PORT PRESS= 2115.925170 CP= -1	PORT # 16 X/C= 0.784 PORT PRESS= 2116.129730 CP= -0.9	PORT # 25 X/C= 0.906 PORT PRESS= 2116.538850 CP= -0.7	PORT # 34 X/C= 0.927 PORT PRESS= 2116.743410 CP= -0.6	PORT # 43 X/C= 0.938 PORT PRESS= 2116.743410 CP= -0.6	PORT # 52 X/C= 0.949 PORT PRESS= 2116.947970 CP= -0.5	PORT # 61 X/C= 0.960 PORT PRESS= 2116.947970 CP= -0.5	PORT # 70 X/C= 0.971 PORT PRESS= 2116.947970 CP= -0.5
PORT # 8 X/C= 0.576 PORT PRESS= 2115.925170 CP= -1	PORT # 17 X/C= 0.8 PORT PRESS= 2116.129730 CP= -0.9	PORT # 26 X/C= 0.917 PORT PRESS= 2116.538850 CP= -0.7	PORT # 35 X/C= 0.938 PORT PRESS= 2116.743410 CP= -0.6	PORT # 44 X/C= 0.949 PORT PRESS= 2116.743410 CP= -0.6	PORT # 53 X/C= 0.960 PORT PRESS= 2116.947970 CP= -0.5	PORT # 62 X/C= 0.971 PORT PRESS= 2116.947970 CP= -0.5	PORT # 71 X/C= 0.982 PORT PRESS= 2116.947970 CP= -0.5
PORT # 9 X/C= 0.608 PORT PRESS= 2115.925170 CP= -1	PORT # 18 X/C= 0.816 PORT PRESS= 2116.129730 CP= -0.9	PORT # 27 X/C= 0.933 PORT PRESS= 2116.538850 CP= -0.7	PORT # 36 X/C= 0.954 PORT PRESS= 2116.743410 CP= -0.6	PORT # 45 X/C= 0.965 PORT PRESS= 2116.743410 CP= -0.6	PORT # 54 X/C= 0.976 PORT PRESS= 2116.947970 CP= -0.5	PORT # 63 X/C= 0.987 PORT PRESS= 2116.947970 CP= -0.5	PORT # 72 X/C= 0.998 PORT PRESS= 2116.947970 CP= -0.5

TABLE III (continued)

## MEASURED SURFACE PRESSURES

70 HZ 65 TEMP (F)				90 PER CENT BURSTS			
ATTNOS PRESS (PSF) 2120.016370							
TUNNEL PRESS (PSF) 2118.379890							
TUNNEL Q (PSF) 1.63648							
TUNNEL VELOC (FPS) 37.2957571							
PORT # 1	X/C= 0.352	2117.357090	PORT # 10	X/C= 0.64	2117.357090	PORT # 19	X/C= 0.332
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625
PORT # 2	X/C= 0.384	2117.357090	PORT # 11	X/C= 0.672	2117.357090	PORT # 20	X/C= 0.848
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625
PORT # 3	X/C= 0.416	2117.357090	PORT # 12	X/C= 0.72	2117.357090	PORT # 21	X/C= 0.864
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625
PORT # 4	X/C= 0.443	2117.357090	PORT # 13	X/C= 0.736	2117.357090	PORT # 22	X/C= 0.88
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625
PORT # 5	X/C= 0.48	2117.357090	PORT # 14	X/C= 0.752	2117.357090	PORT # 23	X/C= 0.896
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625
PORT # 6	X/C= 0.512	2117.357090	PORT # 15	X/C= 0.768	2117.357090	PORT # 24	X/C= 0.912
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625
PORT # 7	X/C= 0.544	2117.357090	PORT # 16	X/C= 0.784	2117.357090	PORT # 25	X/C= 0.928
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625
PORT # 8	X/C= 0.576	2117.357090	PORT # 17	X/C= 0.8	2117.357090	PORT # 26	X/C= 0.944
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625
PORT # 9	X/C= 0.608	2117.357090	PORT # 18	X/C= 0.816	2117.357090	PORT # 27	X/C= 0.96
PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625		PORT PRESS=	CP= -0.625

TABLE IV

## PRESSURE SURVEY DATA

## PRIMARY MODEL

67% Shutter Blades Installed

Ambient Conditions: Temperature = 68°F, Pressure = 30.00 inches Hg

 $f = 0 \text{ Hz}$   
 $q = 20 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	37.8
2	36.8
3	35.8
4	35.3
5	34.8
6	34.8
7	34.8
8	33.8
9	35.8
10	36.8
11	39.8
12	35.8
13	34.3
14	32.3
15	29.3
16	28.3
17	25.8
18	24.8
19	23.8
20	23.3
21	22.8
22	22.3
23	21.3
24	20.8
25	20.3
26	20.0
27	19.8

 $f = 1 \text{ Hz}$   
 $q = 5.0 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	9.3
2	9.1
3	8.8
4	8.7
5	8.6
6	8.6
7	8.6
8	8.3
9	8.8
10	9.0
11	10.0
12	8.8
13	8.3
14	7.8
15	7.4
16	7.2
17	7.0
18	6.8
19	6.5
20	6.2
21	6.2
22	6.0
23	5.9
24	5.8
25	5.6
26	5.5
27	5.4



TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

67% Shutter Blades Installed

Ambient Conditions: Temperature = 68°F, Pressure = 30.00 inches Hg

 $f = 2 \text{ Hz}$   
 $q = 4.5 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	8.2
2	7.9
3	7.8
4	7.6
5	7.5
6	7.5
7	7.6
8	7.3
9	7.8
10	8.0
11	8.6
12	7.8
13	7.3
14	7.0
15	6.6
16	6.3
17	6.2
18	6.0
19	5.6
20	5.4
21	5.3
22	5.2
23	5.2
24	5.1
25	5.0
26	4.9
27	4.8

 $f = 4 \text{ Hz}$   
 $q = 3.8 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	7.1
2	6.9
3	6.7
4	6.5
5	6.5
6	6.5
7	6.5
8	6.3
9	6.7
10	6.8
11	7.4
12	6.7
13	6.2
14	5.9
15	5.5
16	5.4
17	5.2
18	5.1
19	4.9
20	4.5
21	4.4
22	4.3
23	4.3
24	4.2
25	4.1
26	4.0
27	4.0

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

67% Shutter Blades Installed

Ambient Conditions: Temperature = 68°F, Pressure = 30.00 inches Hg

 $f = 6 \text{ Hz}$   
 $q = 3.8 \text{ cm H}_2\text{O}$ 
 $f = 25 \text{ Hz}$   
 $q = 4.5 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)	Static Port Number	Pressure (cm H <sub>2</sub> O)
1	7.0	1	7.8
2	6.7	2	7.7
3	6.6	3	7.6
4	6.5	4	7.5
5	6.3	5	7.4
6	6.4	6	7.3
7	6.5	7	7.2
8	6.1	8	7.0
9	6.7	9	7.6
10	6.8	10	7.8
11	7.4	11	8.3
12	6.7	12	7.6
13	6.3	13	7.0
14	5.9	14	6.6
15	5.7	15	6.3
16	5.5	16	6.1
17	5.2	17	5.8
18	5.1	18	5.8
19	4.7	19	5.6
20	4.5	20	5.3
21	4.5	21	5.3
22	4.2	22	5.3
23	4.2	23	5.2
24	4.2	24	5.1
25	4.1	25	5.0
26	4.1	26	4.8
27	4.0	27	4.8

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

67% Shutter Blades Installed

Ambient Conditions: Temperature = 68°F, Pressure = 30.00 inches Hg

 $f = 30 \text{ Hz}$   
 $q = 5.0 \text{ cm H}_2\text{O}$ 
 $f = 40 \text{ Hz}$   
 $q = 4.5 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)	Static Port Number	Pressure (cm H <sub>2</sub> O)
1	7.8	1	6.8
2	7.6	2	6.7
3	7.4	3	6.6
4	7.3	4	6.4
5	7.3	5	6.3
6	7.3	6	6.3
7	7.3	7	6.3
8	7.1	8	6.0
9	7.8	9	6.6
10	7.8	10	6.8
11	8.8	11	7.3
12	7.8	12	6.8
13	7.0	13	6.3
14	6.8	14	5.8
15	6.6	15	5.6
16	6.4	16	5.5
17	6.0	17	5.3
18	5.8	18	5.0
19	5.6	19	4.8
20	5.3	20	4.7
21	5.3	21	4.6
22	5.2	22	4.4
23	5.2	23	4.3
24	5.1	24	4.3
25	5.1	25	4.2
26	5.0	26	4.1
27	4.8	27	4.0

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

67% Shutter Blades Installed

Ambient Conditions: Temperature = 68°F, Pressure = 30.00 inches Hg

 $f = 50 \text{ Hz}$   
 $q = 5.0 \text{ cm H}_2\text{O}$ 
 $f = 60 \text{ Hz}$   
 $q = 3.8 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)	Static Port Number	Pressure (cm H <sub>2</sub> O)
1	8.3	1	6.8
2	8.1	2	6.6
3	8.0	3	6.5
4	7.8	4	6.4
5	7.6	5	6.3
6	7.6	6	6.3
7	7.6	7	6.3
8	7.2	8	6.0
9	7.8	9	6.5
10	8.0	10	6.6
11	8.6	11	7.2
12	7.6	12	6.5
13	7.1	13	6.0
14	6.8	14	5.6
15	6.3	15	5.4
16	6.2	16	5.3
17	6.0	17	5.2
18	5.8	18	4.8
19	5.4	19	4.6
20	5.3	20	4.5
21	5.2	21	4.5
22	5.1	22	4.4
23	5.0	23	4.3
24	4.8	24	4.3
25	4.6	25	4.2
26	4.5	26	4.2
27	4.4	27	4.0

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

67% Shutter Blades Installed

Ambient Conditions: Temperature = 68°F, Pressure = 30.00 inches Hg

 $f = 70 \text{ Hz}$   
 $q = 3.8 \text{ cm H}_2\text{O}$ 
 $f = 80 \text{ Hz}$   
 $q = 5.8 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)	Static Port Number	Pressure (cm H <sub>2</sub> O)
1	6.8	1	7.6
2	6.6	2	7.4
3	6.3	3	7.2
4	6.2	4	7.0
5	6.2	5	7.0
6	6.2	6	7.0
7	6.2	7	7.0
8	5.8	8	6.8
9	6.4	9	7.6
10	6.6	10	7.8
11	7.0	11	8.6
12	6.4	12	8.0
13	6.0	13	7.3
14	5.6	14	7.0
15	5.4	15	6.8
16	5.2	16	6.6
17	5.0	17	6.3
18	4.8	18	6.1
19	4.6	19	5.8
20	4.4	20	5.6
21	4.4	21	5.6
22	4.4	22	5.5
23	4.3	23	5.4
24	4.2	24	5.3
25	4.2	25	5.2
26	4.1	26	5.2
27	4.0	27	5.0

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

67% Shutter Blades Installed

Ambient Conditions: Temperature = 68°F, Pressure = 30.00 inches hg

 $f = 90 \text{ Hz}$   
 $q = 4.5 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	7.0
2	6.8
3	6.6
4	6.5
5	6.3
6	6.4
7	6.4
8	6.2
9	6.8
10	6.8
11	7.4
12	6.6
13	6.1
14	5.8
15	5.6
16	5.4
17	5.2
18	5.0
19	4.8
20	4.6
21	4.6
22	4.4
23	4.4
24	4.4
25	4.3
26	4.2
27	4.0

 $f = 100 \text{ Hz}$   
 $q = 3.8 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	6.8
2	6.6
3	6.5
4	6.4
5	6.2
6	6.3
7	6.3
8	6.0
9	6.5
10	6.6
11	7.0
12	6.4
13	5.9
14	5.7
15	5.4
16	5.3
17	5.0
18	4.8
19	4.6
20	4.4
21	4.4
22	4.3
23	4.3
24	4.2
25	4.1
26	4.1
27	4.0

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

98% Shutter Blades Installed

Ambient Conditions: Temperature = 72°F, Pressure = 30.08 inches Hg

 $f = 1 \text{ Hz}$   
 $q = 3.0 \text{ cm H}_2\text{O}$ 
 $f = 2 \text{ Hz}$   
 $q = 2.0 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)	Static Port Number	Pressure (cm H <sub>2</sub> O)
1	5.0	1	4.0
2	4.9	2	3.9
3	4.8	3	3.7
4	4.5	4	3.5
5	4.5	5	3.5
6	4.5	6	3.5
7	4.5	7	3.5
8	4.4	8	3.3
9	5.0	9	3.6
10	5.0	10	3.6
11	5.3	11	4.0
12	5.0	12	3.6
13	4.5	13	3.3
14	4.3	14	3.2
15	4.0	15	3.0
16	3.9	16	2.9
17	3.5	17	2.9
18	3.7	18	2.7
19	3.5	19	2.7
20	3.3	20	2.5
21	3.3	21	2.5
22	3.3	22	2.3
23	3.2	23	2.3
24	3.1	24	2.3
25	3.0	25	2.1
26	3.0	26	2.1
27	3.0	27	2.0

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

98% Shutter Blades Installed

Ambient Conditions: Temperature = 72°F, Pressure = 30.08 inches Hg

 $f = 4 \text{ Hz}$   
 $q = 0.5 \text{ cm H}_2\text{O}$ 
 $f = 6 \text{ Hz}$   
 $q = 0.5 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)	Static Port Number	Pressure (cm H <sub>2</sub> O)
1	1.3	1	0.7
2	1.2	2	0.6
3	1.1	3	0.5
4	1.0	4	0.5
5	1.0	5	0.5
6	1.0	6	0.5
7	1.0	7	0.5
8	1.0	8	0.5
9	1.0	9	0.5
10	1.0	10	0.5
11	1.0	11	0.5
12	0.9	12	0.5
13	0.7	13	0.3
14	0.6	14	0.3
15	0.6	15	0.3
16	0.5	16	0.3
17	0.5	17	0.3
18	0.7	18	0.5
19	0.5	19	0.0
20	0.3	20	0.0
21	0.3	21	0.0
22	0.3	22	-0.1
23	0.2	23	-0.1
24	0.2	24	-0.1
25	0.2	25	-0.1
26	0.2	26	-0.2
27	0.1	27	-0.2



TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

98% Shutter Blades Installed

Ambient Conditions: Temperature = 65°F, Pressure = 30.06 inches Hg

 $f = 25 \text{ Hz}$   
 $q = 1.0 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	1.5
2	1.5
3	1.5
4	1.5
5	1.5
6	1.5
7	1.5
8	1.5
9	1.5
10	1.5
11	2.0
12	1.6
13	1.5
14	1.4
15	1.2
16	1.2
17	1.2
18	1.2
19	1.2
20	1.0
21	1.0
22	1.0
23	0.9
24	0.9
25	0.9
26	0.9
27	0.8

 $f = 30 \text{ Hz}$   
 $q = 2.0 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	1.5
2	1.5
3	1.5
4	1.5
5	1.5
6	1.5
7	1.5
8	1.5
9	1.5
10	1.5
11	1.5
12	1.5
13	1.4
14	1.4
15	1.4
16	1.3
17	1.3
18	1.3
19	1.3
20	1.2
21	1.2
22	1.2
23	1.2
24	1.2
25	1.2
26	1.2
27	1.2

AD-A096 386

NAVAL POSTGRADUATE SCHOOL MONTEREY CA

F/6 20/4

EFFECTS OF OSCILLATION FREQUENCY AND AMPLITUDE ON SEPARATION IN--ETC(U)

SEP 80 M FOX

UNCLASSIFIED

NL

2 of 2

48/4



END

DATE

FILED

4-81

DTIC

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

98% Shutter Blades Installed

Ambient Conditions: Temperature = 65°F, Pressure = 30.06 inches Hg

 $f = 40 \text{ Hz}$   
 $q = 2.0 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	1.2
2	1.2
3	1.2
4	1.2
5	1.2
6	1.2
7	1.2
8	1.2
9	1.2
10	1.2
11	1.4
12	1.3
13	1.2
14	1.2
15	1.2
16	1.1
17	1.1
18	1.2
19	1.2
20	1.2
21	1.2
22	1.2
23	1.2
24	1.1
25	1.1
26	1.1
27	1.1

 $f = 50 \text{ Hz}$   
 $q = 2.2 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	2.5
2	2.5
3	2.4
4	2.4
5	2.4
6	2.4
7	2.4
8	2.4
9	2.4
10	2.2
11	2.5
12	2.2
13	2.0
14	2.0
15	1.8
16	1.8
17	1.7
18	1.7
19	1.6
20	1.5
21	1.5
22	1.5
23	1.4
24	1.3
25	1.2
26	1.1
27	1.0

TABLE IV (continued)

## PRESSURE SURVEY DATA

## PRIMARY MODEL

98% Shutter Blades Installed

Ambient Conditions: Temperature 65°F, Pressure 30.06 inches Hg

 $f = 60 \text{ Hz}$   
 $q = 1.0 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	1.0
2	1.0
3	1.0
4	1.0
5	1.0
6	1.0
7	1.0
8	1.0
9	1.0
10	1.0
11	1.0
12	0.9
13	0.9
14	0.9
15	0.8
16	0.8
17	0.8
18	0.7
19	0.7
20	0.7
21	0.7
22	0.6
23	0.6
24	0.6
25	0.6
26	0.5
27	0.5

 $f = 70 \text{ Hz}$   
 $q = 0.8 \text{ cm H}_2\text{O}$ 

Static Port Number	Pressure (cm H <sub>2</sub> O)
1	0.5
2	0.5
3	0.5
4	0.5
5	0.5
6	0.5
7	0.5
8	0.5
9	0.5
10	0.5
11	0.5
12	0.5
13	0.5
14	0.5
15	0.5
16	0.5
17	0.5
18	0.5
19	0.5
20	0.5
21	0.5
22	0.5
23	0.5
24	0.4
25	0.4
26	0.3
27	0.3

## LIST OF REFERENCES

1. Karlsson, S. K. F., An Unsteady Turbulent Boundary Layer, Ph. D. Thesis, Johns Hopkins University, 1958.
2. Nickerson, R. J., The Effect of Free Stream Oscillation on the Laminar Boundary Layer on a Flat Plate, Sc. O. Thesis, Massachusetts Institute of Technology, 1957.
3. Despard, R. A., Laminar Boundary Layer Separation in Oscillating Flow, Ph. D. Thesis, Naval Postgraduate School, June 1969.
4. Miller, J. A., Transition in Oscillating Blasius Flow, Ph. D. Thesis, Illinois Institute of Technology June 1963.
5. AGARD Conference Proceedings No. 227, Unsteady Boundary Layers, Separated and Attached, Demetri P. Telionis, September 1977.
6. Allen, T. J., Pressure Distribution on an Airfoil in Oscillating Flow, M. S. Thesis, Naval Postgraduate School, June 1969.
7. Jacobs, K. J., Intensity Distribution in the Oscillating Turbulent Boundary Layer on a Flat Plate, M. S. Thesis, Naval Postgraduate School, March 1968.
8. Bradshaw, P., Introduction to Turbulence and Its Measurement, Pergamon Press, 1975.

# INITIAL DISTRIBUTION LIST

	No. Copies
1. Defense Technical Information Center Cameron Station Alexandria, Virginia 22314	2
2. Library, Code 0142 Naval Postgraduate School Monterey, California 93940	2
3. Department Chairman, Code 67 Department of Aeronautics Naval Postgraduate School Monterey, California 93940	1
4. Assoc. Prof. J. A. Miller, Code 67Mo Department of Aeronautics Naval Postgraduate School Monterey, California 93940	1
5. LT Martin Fox, USN 13125 Wilcox Road #4B4 Largo, Florida 33540	1

ATE  
LMED  
-8